



# **OPA124**

# Low Noise Precision *Difet*® OPERATIONAL AMPLIFIER

# **FEATURES**

LOW NOISE: 6nV/√Hz (10kHz)
 LOW BIAS CURRENT: 1pA max

LOW OFFSET: 250μV max
 LOW DRIFT: 2μV/°C max

 HIGH OPEN-LOOP GAIN: 120dB min
 HIGH COMMON-MODE REJECTION: 100dB min

 AVAILABLE IN 8-PIN PLASTIC DIP AND 8-PIN SOIC PACKAGES

# **DESCRIPTION**

The OPA124 is a precision monolithic FET operational amplifier using a **Difet** (dielectrical isolation) manufacturing process. Outstanding DC and AC performance characteristics allow its use in the most critical instrumentation applications.


Bias current, noise, voltage offset, drift, open-loop gain, common-mode rejection and power supply rejection are superior to BIFET and CMOS amplifiers. *Difet* fabrication achieves extremely low input bias currents without compromising input voltage noise performance. Low input bias current is maintained over a wide input common-mode voltage range with unique cascode circuitry. This cascode design also allows high precision input specifications and reduced susceptibility to flicker noise. Laser trimming of thin-film resistors gives very low offset and drift.

Compared to the popular OPA111, the OPA124 gives comparable performance and is available in an 8-pin PDIP and 8-pin SOIC package.

BIFET® National Semiconductor Corp., *Difet*® Burr-Brown Corp.

### **APPLICATIONS**

- PRECISION PHOTODIODE PREAMP
- MEDICAL EQUIPMENT
- OPTOELECTRONICS
- DATA ACQUISITION
- TEST EQUIPMENT



NOTES: (1) Omitted on SOIC. (2) Patented.

International Airport Industrial Park • Mailing Address: PO Box 11400, Tucson, AZ 85734 • Street Address: 6730 S. Tucson Blvd., Tucson, AZ 85706 • Tel: (520) 746-1111 • Twx: 910-952-1111 Internet: http://www.burr-brown.com/ • FAXLine: (800) 548-6133 (US/Canada Only) • Cable: BBRCORP • Telex: 066-6491 • FAX: (520) 889-1510 • Immediate Product Info: (800) 548-6132

# **SPECIFICATIONS**

### **ELECTRICAL**

At  $V_{CC}$  = ±15VDC and  $T_A$  = +25°C, unless otherwise noted.


		OPA124U, P		OPA124UA, PA		OPA124PB		]			
PARAMETER	CONDITION	MIN	TYP	MAX	MIN	TYP	MAX	MIN	TYP	MAX	UNITS
INPUT NOISE Voltage, $f_O = 10Hz^{(4)}$ $f_O = 100Hz^{(4)}$			40 15	80 40		*	*		*	*	nV/√Hz nV/√Hz
$f_{O} = 1 \text{kHz}^{(4)}$ $f_{O} = 10 \text{kHz}^{(5)}$ $f_{B} = 10 \text{Hz to } 10 \text{kHz}^{(5)}$			8 6 0.7	15 8 1.2		* * *	* * *		* * *	* * *	nV/√ <del>Hz</del> nV/√ <del>Hz</del> μVrms
$\begin{split} f_B &= 0.1 \text{Hz to 10Hz} \\ \text{Current, } f_B &= 0.1 \text{Hz to 10Hz} \\ f_O &= 0.1 \text{Hz thru 20kHz} \end{split}$			1.6 9.5 0.5	3.3 15 0.8		* * *	* * *		* * *	* * *	μVp-p fAp-p fA/√Hz
OFFSET VOLTAGE <sup>(1)</sup> Input Offset Voltage vs Temperature Supply Rejection vs Temperature	$V_{CM} = 0 VDC$ $T_A = T_{MIN} \text{ to } T_{MAX}$ $V_{CC} = \pm 10 V \text{ to } \pm 18 V$ $T_A = T_{MIN} \text{ to } T_{MAX}$	88 84	±200 ±4 110 100	±800 ±7.5	90 86	±150 ±2 *	±500 ±4	100 90	±100 ±1 *	±250 ±2	μV μV/°C dB dB
BIAS CURRENT <sup>(1)</sup> Input Bias Current	V <sub>CM</sub> = 0VDC		±1	±5		±0.5	<u>±2</u>		±0.35	±1	pA
OFFSET CURRENT <sup>(1)</sup> Input Offset Current	V <sub>CM</sub> = 0VDC		±1	±5		±0.5	±1		±0.25	±0.5	pA
IMPEDANCE Differential Common-Mode			10 <sup>13</sup>    1 10 <sup>14</sup>    3			* *			* *		Ω    pF Ω    pF
VOLTAGE RANGE Common-Mode Input Range Common-Mode Rejection vs Temperature	$V_{IN} = \pm 10 VDC$ $T_A = T_{MIN} \text{ to } T_{MAX}$	±10 92 86	±11 110 100		* 94 *	* * *		* 100 90	* * *		V dB dB
OPEN-LOOP GAIN, DC Open-Loop Voltage Gain	$R_L \ge 2k\Omega$	106	125		*	*		120	*		dB
FREQUENCY RESPONSE Unity Gain, Small Signal Full Power Response Slew Rate THD Settling Time, 0.1% 0.01%	$20\text{Vp-p, R}_{L} = 2k\Omega$ $\text{V}_{O} = \pm 10\text{V, R}_{L} = 2k\Omega$ $\text{Gain} = -1, \text{R}_{L} = 2k\Omega$ $10\text{V Step}$	16 1	1.5 32 1.6 0.0003 6 10		* *	* * * * *		*	* * * * *		MHz kHz V/μs % μs μs
Overload Recovery, 50% Overdrive <sup>(2)</sup>	Gain = −1		5			*			*		μs
RATED OUTPUT Voltage Output Current Output Output Resistance Load Capacitance Stability Short Circuit Current	$R_L = 2k\Omega$ $V_O = \pm 10VDC$ DC, Open Loop $Gain = +1$	±11 ±5.5	±12 ±10 100 1000 40		* *	* * * *		* *	* * * *		V mA Ω pF mA
POWER SUPPLY Rated Voltage Voltage Range, Derated Current, Quiescent	I <sub>O</sub> = 0mADC	±5	±15	±18 3.5	*	*	*	*	*	*	VDC VDC mA
TEMPERATURE RANGE Specification Storage θ Junction-Ambient: PDIP SOIC	T <sub>MIN</sub> and T <sub>MAX</sub>	-25 -65	90 100	+85 +125	* *	* *	* *	*	* *	*	°C °C/W °C/W


<sup>\*</sup> Specification same as OPA124U, P

NOTES: (1) Offset voltage, offset current, and bias current are measured with the units fully warmed up. For performance at other temperatures see Typical Performance Curves. (2) Overload recovery is defined as the time required for the output to return from saturation to linear operation following the removal of a 50% input overdrive. (3) For performance at other temperatures see Typical Performance Curves. (4) Sample tested, 98% confidence. (5) Guaranteed by design.



#### **CONNECTION DIAGRAMS**





### PACKAGE/ORDERING INFORMATION

PRODUCT	PACKAGE	PACKAGE DRAWING NUMBER <sup>(1)</sup>	TEMPERATURE RANGE	BIAS CURRENT pA, max	OFFSET DRIFT μV/°C, max
OPA124U	8-Lead SOIC	182	−25°C to +85°C	5	7.5
OPA124P	8-Pin Plastic DIP	006	−25°C to +85°C	5	7.5
OPA124UA	8-Lead SOIC	182	−25°C to +85°C	2	4
OPA124PA	8-Pin Plastic DIP	006	−25°C to +85°C	2	4
OPA124PB	8-Pin Plastic DIP	006	−25°C to +85°C	1	2

NOTE: (1) For detailed drawing and dimension table, please see end of data sheet, or Appendix C of Burr-Brown IC Data Book.

#### **ABSOLUTE MAXIMUM RATINGS(1)**

Supply	±18VDC
Internal Power Dissipation <sup>(2)</sup>	750mW
Differential Input Voltage(3)	±36VDC
Input Voltage Range(3)	±18VDC
Storage Temperature Range	–65°C to +150°C
Operating Temperature Range	40°C to +125°C
Lead Temperature (soldering, 10s)	+300°C
Output Short Circuit Duration(4)	Continuous
Junction Temperature	+175°C
1	

NOTES: (1) Stresses above these ratings may cause permanent damage. (2) Packages must be derated based on  $\theta_{JA} = 90^{\circ}\text{C/W}$  for PDIP and  $100^{\circ}\text{C/W}$  for SOIC. (3) For supply voltages less than ±18VDC, the absolute maximum input voltage is equal to +18V > V\_{IN} > -V\_{CC} - 6V. See Figure 2. (4) Short circuit may be to power supply common only. Rating applies to +25°C ambient. Observe dissipation limit and  $T_{J}$ .




This integrated circuit can be damaged by ESD. Burr-Brown recommends that all integrated circuits be handled with appropriate precautions. Failure to observe proper handling and installation procedures can cause damage.


ESD damage can range from subtle performance degradation to complete device failure. Precision integrated circuits may be more susceptible to damage because very small parametric changes could cause the device not to meet its published specifications.


The information provided herein is believed to be reliable; however, BURR-BROWN assumes no responsibility for inaccuracies or omissions. BURR-BROWN assumes no responsibility for the use of this information, and all use of such information shall be entirely at the user's own risk. Prices and specifications are subject to change without notice. No patent rights or licenses to any of the circuits described herein are implied or granted to any third party. BURR-BROWN does not authorize or warrant any BURR-BROWN product for use in life support devices and/or systems.


# **TYPICAL PERFORMANCE CURVES**


At  $T_A = +25$ °C, and  $V_{CC} = \pm 15$ VDC, unless otherwise noted.




















# TYPICAL PERFORMANCE CURVES (CONT)


At  $T_A = +25$ °C, and  $V_{CC} = \pm 15$ VDC, unless otherwise noted.













5


# **TYPICAL PERFORMANCE CURVES (CONT)**


At  $T_A = +25$ °C, and  $V_{CC} = \pm 15$ VDC, unless otherwise noted.




















# **TYPICAL PERFORMANCE CURVES (CONT)**

At  $T_A = +25$ °C, and  $V_{CC} = \pm 15$ VDC, unless otherwise noted.









# **APPLICATIONS INFORMATION**

### **OFFSET VOLTAGE ADJUSTMENT**

The OPA124 offset voltage is laser-trimmed and will require no further trim for most applications. In order to reduce layout leakage errors, the offset adjust capability has been removed from the SOIC versions (OPA124UA and OPA124U). The PDIP versions (OPA124PB, OPA124PA, and OPA124P) do have pins available for offset adjustment. As with most amplifiers, externally trimming the remaining offset can change drift performance by about  $0.3\mu V/^{\circ}C$  for each  $100\mu V$  of adjusted offset. The correct circuit configuration for offset adjust for the PDIP packages is shown in Figure 1.

### INPUT PROTECTION

Conventional monolithic FET operational amplifiers require external current-limiting resistors to protect their inputs against destructive currents that can flow when input FET gate-to-substrate isolation diodes are forward-biased. Most BIFET amplifiers can be destroyed by the loss of  $-V_{CC}$ .

Unlike BIFET amplifiers, the **Difet** OPA124 requires input current limiting resistors only if its input voltage is greater than 6V more negative than  $-V_{CC}$ . A  $10k\Omega$  series resistor will limit input current to a safe level with up to  $\pm 15$ V input levels, even if both supply voltages are lost (Figure 2).

Static damage can cause subtle changes in amplifier input characteristics without necessarily destroying the device. In precision operational amplifiers (both bipolar and FET types), this may cause a noticeable degradation of offset voltage and drift. Static protection is recommended when handling any precision IC operational amplifier.

#### **GUARDING AND SHIELDING**

As in any situation where high impedances are involved, careful shielding is required to reduce "hum" pickup in input leads. If large feedback resistors are used, they should also be shielded along with the external input circuitry.

Leakage currents across printed circuit boards can easily exceed the bias current of the OPA124. To avoid leakage problems, the OPA124 should be soldered directly into a printed circuit board. Utmost care must be used in planning the board layout. A "guard" pattern should completely surround the high impedance input leads and should be connected to a low impedance point which is at the signal input potential.

The amplifier substrate should be connected to any input shield or guard via pin 8 minimizing both leakage and noise pickup (see Figure 3).

If guarding is not required, pin 8 should be connected to ground.




FIGURE 1. Offset Voltage Trim for PDIP packages.




FIGURE 2. Input Current vs Input Voltage with  $\pm V_{\rm CC}$  Pins Grounded.




FIGURE 3. Connection of Input Guard.



### PACKAGE OPTION ADDENDUM



i.com 22-Oct-2007

### PACKAGING INFORMATION

Orderable Device	Status <sup>(1)</sup>	Package Type	Package Drawing	Pins	Package Qty	Eco Plan <sup>(2)</sup>	Lead/Ball Finish	MSL Peak Temp (3)
OPA124P	OBSOLETE	PDIP	Р	8		TBD	Call TI	Call TI
OPA124PA	OBSOLETE	PDIP	Р	8		TBD	Call TI	Call TI
OPA124PA2	OBSOLETE	PDIP	Р	8		TBD	Call TI	Call TI
OPA124PB	OBSOLETE	PDIP	Р	8		TBD	Call TI	Call TI
OPA124U	ACTIVE	SOIC	D	8	100	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-3-260C-168 HR
OPA124U/2K5	ACTIVE	SOIC	D	8	2500	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-3-260C-168 HR
OPA124U/2K5G4	ACTIVE	SOIC	D	8	2500	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-3-260C-168 HR
OPA124UA	ACTIVE	SOIC	D	8	100	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-3-260C-168 HR
OPA124UA/2K5	ACTIVE	SOIC	D	8	2500	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-3-260C-168 HR
OPA124UA/2K5E4	ACTIVE	SOIC	D	8	2500	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-3-260C-168 HR
OPA124UAE4	ACTIVE	SOIC	D	8	100	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-3-260C-168 HR
OPA124UAG4	ACTIVE	SOIC	D	8	100	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-3-260C-168 HR
OPA124UE4	ACTIVE	SOIC	D	8	100	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-3-260C-168 HR
OPA124UG4	ACTIVE	SOIC	D	8	100	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-3-260C-168 HR

<sup>(1)</sup> The marketing status values are defined as follows:

ACTIVE: Product device recommended for new designs.

LIFEBUY: TI has announced that the device will be discontinued, and a lifetime-buy period is in effect.

NRND: Not recommended for new designs. Device is in production to support existing customers, but TI does not recommend using this part in a new design.

**PREVIEW:** Device has been announced but is not in production. Samples may or may not be available.

**OBSOLETE:** TI has discontinued the production of the device.

(2) Eco Plan - The planned eco-friendly classification: Pb-Free (RoHS), Pb-Free (RoHS Exempt), or Green (RoHS & no Sb/Br) - please check http://www.ti.com/productcontent for the latest availability information and additional product content details.

TBD: The Pb-Free/Green conversion plan has not been defined.

**Pb-Free** (RoHS): TI's terms "Lead-Free" or "Pb-Free" mean semiconductor products that are compatible with the current RoHS requirements for all 6 substances, including the requirement that lead not exceed 0.1% by weight in homogeneous materials. Where designed to be soldered at high temperatures, TI Pb-Free products are suitable for use in specified lead-free processes.

**Pb-Free (RoHS Exempt):** This component has a RoHS exemption for either 1) lead-based flip-chip solder bumps used between the die and package, or 2) lead-based die adhesive used between the die and leadframe. The component is otherwise considered Pb-Free (RoHS compatible) as defined above.

**Green (RoHS & no Sb/Br):** TI defines "Green" to mean Pb-Free (RoHS compatible), and free of Bromine (Br) and Antimony (Sb) based flame retardants (Br or Sb do not exceed 0.1% by weight in homogeneous material)

(3) MSL, Peak Temp. -- The Moisture Sensitivity Level rating according to the JEDEC industry standard classifications, and peak solder temperature.

**Important Information and Disclaimer:** The information provided on this page represents TI's knowledge and belief as of the date that it is provided. TI bases its knowledge and belief on information provided by third parties, and makes no representation or warranty as to the accuracy of such information. Efforts are underway to better integrate information from third parties. TI has taken and continues to take reasonable steps to provide representative and accurate information but may not have conducted destructive testing or chemical analysis on incoming materials and chemicals. TI and TI suppliers consider certain information to be proprietary, and thus CAS numbers and other limited



to Customer on an annual basis.

# **PACKAGE OPTION ADDENDUM**

22-Oct-2007

information may not be available for release.
In no event shall TI's liability arising out of such information exceed the total purchase price of the TI part(s) at issue in this document sold by TI

### **IMPORTANT NOTICE**

Texas Instruments Incorporated and its subsidiaries (TI) reserve the right to make corrections, modifications, enhancements, improvements, and other changes to its products and services at any time and to discontinue any product or service without notice. Customers should obtain the latest relevant information before placing orders and should verify that such information is current and complete. All products are sold subject to TI's terms and conditions of sale supplied at the time of order acknowledgment.

TI warrants performance of its hardware products to the specifications applicable at the time of sale in accordance with TI's standard warranty. Testing and other quality control techniques are used to the extent TI deems necessary to support this warranty. Except where mandated by government requirements, testing of all parameters of each product is not necessarily performed.

TI assumes no liability for applications assistance or customer product design. Customers are responsible for their products and applications using TI components. To minimize the risks associated with customer products and applications, customers should provide adequate design and operating safeguards.

TI does not warrant or represent that any license, either express or implied, is granted under any TI patent right, copyright, mask work right, or other TI intellectual property right relating to any combination, machine, or process in which TI products or services are used. Information published by TI regarding third-party products or services does not constitute a license from TI to use such products or services or a warranty or endorsement thereof. Use of such information may require a license from a third party under the patents or other intellectual property of the third party, or a license from TI under the patents or other intellectual property of TI.

Reproduction of TI information in TI data books or data sheets is permissible only if reproduction is without alteration and is accompanied by all associated warranties, conditions, limitations, and notices. Reproduction of this information with alteration is an unfair and deceptive business practice. TI is not responsible or liable for such altered documentation. Information of third parties may be subject to additional restrictions.

Resale of TI products or services with statements different from or beyond the parameters stated by TI for that product or service voids all express and any implied warranties for the associated TI product or service and is an unfair and deceptive business practice. TI is not responsible or liable for any such statements.

TI products are not authorized for use in safety-critical applications (such as life support) where a failure of the TI product would reasonably be expected to cause severe personal injury or death, unless officers of the parties have executed an agreement specifically governing such use. Buyers represent that they have all necessary expertise in the safety and regulatory ramifications of their applications, and acknowledge and agree that they are solely responsible for all legal, regulatory and safety-related requirements concerning their products and any use of TI products in such safety-critical applications, notwithstanding any applications-related information or support that may be provided by TI. Further, Buyers must fully indemnify TI and its representatives against any damages arising out of the use of TI products in such safety-critical applications.

TI products are neither designed nor intended for use in military/aerospace applications or environments unless the TI products are specifically designated by TI as military-grade or "enhanced plastic." Only products designated by TI as military-grade meet military specifications. Buyers acknowledge and agree that any such use of TI products which TI has not designated as military-grade is solely at the Buyer's risk, and that they are solely responsible for compliance with all legal and regulatory requirements in connection with such use.

TI products are neither designed nor intended for use in automotive applications or environments unless the specific TI products are designated by TI as compliant with ISO/TS 16949 requirements. Buyers acknowledge and agree that, if they use any non-designated products in automotive applications, TI will not be responsible for any failure to meet such requirements.

Following are URLs where you can obtain information on other Texas Instruments products and application solutions:

Products		Applications	
Amplifiers	amplifier.ti.com	Audio	www.ti.com/audio
Data Converters	dataconverter.ti.com	Automotive	www.ti.com/automotive
DSP	dsp.ti.com	Broadband	www.ti.com/broadband
Interface	interface.ti.com	Digital Control	www.ti.com/digitalcontrol
Logic	logic.ti.com	Military	www.ti.com/military
Power Mgmt	power.ti.com	Optical Networking	www.ti.com/opticalnetwork
Microcontrollers	microcontroller.ti.com	Security	www.ti.com/security
RFID	www.ti-rfid.com	Telephony	www.ti.com/telephony
Low Power Wireless	www.ti.com/lpw	Video & Imaging	www.ti.com/video
		Wireless	www.ti.com/wireless

Mailing Address: Texas Instruments, Post Office Box 655303, Dallas, Texas 75265 Copyright © 2007, Texas Instruments Incorporated