

# ADC08D1500 High Performance, Low Power, Dual 8-Bit, 1.5 GSPS A/D Converter

# **General Description**

The ADC08D1500 is a dual, low power, high performance CMOS analog-to-digital converter that digitizes signals to 8 bits resolution at sample rates up to 1.7 GSPS. Consuming a typical 1.8 Watts at 1.5 GSPS from a single 1.9 Volt supply, this device is guaranteed to have no missing codes over the full operating temperature range. The unique folding and interpolating architecture, the fully differential comparator design, the innovative design of the internal sample-and-hold amplifier and the self-calibration scheme enable a very flat response of all dynamic parameters beyond Nyquist, producing a high 7.25 ENOB with a 748 MHz input signal and a 1.5 GHz sample rate while providing a 10-18 C.E.R. Output formatting is binary and the LVDS digital outputs are compatible with IEEE 1596.3-1996, with the exception of an adjustable common mode voltage between 0.8V and 1.2V.

Each converter has a 1:2 demultiplexer that feeds two LVDS buses and reduces the output data rate on each bus to half the sample rate. The two converters can be interleaved and used as a single 3 GSPS ADC.

The converter typically consumes less than 3.5 mW in the Power Down Mode and is available in a 128-lead, thermally enhanced exposed pad LQFP and operates over the Industrial (-40°C  $\leq T_A \leq +85$ °C) temperature range.

#### **Features**

- Internal Sample-and-Hold
- Single +1.9V ±0.1V Operation

- Choice of SDR or DDR output clocking
- Interleave Mode for 2x Sample Rate
- Multiple ADC Synchronization Capability
- Guaranteed No Missing Codes
- Serial Interface for Extended Control
- Fine Adjustment of Input Full-Scale Range and Offset
- Duty Cycle Corrected Sample Clock

# **Key Specifications**

■ Resolution	8 Bits
<ul><li>Max Conversion Rate</li></ul>	1.5 GSPS (min)
■ Error Rate	10 <sup>-18</sup> (typ)
■ ENOB @ 748 MHz Input	7.25 Bits (typ)
■ DNL	±0.15 LSB (typ)
- Davies Consumenties	


Power Consumption

OperatingPower Down Mode1.8 W (typ)3.5 mW (typ)

# **Applications**

- Direct RF Down Conversion
- Digital Oscilloscopes
- Satellite Set-top boxes
- Communications Systems
- Test Instrumentation


# **Block Diagram**



# **Ordering Information**

Industrial Temperature Range (-40°C < T <sub>A</sub> < +85°C)	NS Package
ADC08D1500CIYB	128-Pin Exposed Pad LQFP
ADC08D1500DEV	Development Board
ADC08D1500EVAL	Evaluation Board

# **Pin Configuration**



<sup>\*</sup> Exposed pad on back of package must be soldered to ground plane to ensure rated performance.

# **Pin Descriptions and Equivalent Circuits**

Pin Funct Pin No.	Symbol	Equivalent Circuit	Description
3	OutV / SCLK	V <sub>A</sub> 50k GND	Output Voltage Amplitude and Serial Interface Clock. Tie this pin high for normal differential DCLK and data amplitude. Ground this pin for a reduced differential output amplitude and reduced power consumption. See 1.1.6 The LVDS Outputs. When the extended control mode is enabled, this pin functions as the SCLK input which clocks in the serial data. See 1.2 NORMAL/EXTENDED CONTROL for details on the extended control mode. See 1.3 THE SERIAL INTERFACE for description of the serial interface.
4	OutEdge / DDR / SDATA	SDATA  VA  50k 200k  DDR  DDR  SDATA	DCLK Edge Select, Double Data Rate Enable and Serial Data Input. This input sets the output edge of DCLK+ at which the output data transitions. (See 1.1.5.2 OutEdge Setting). When this pin is floating or connected to 1/2 the supply voltage, DDR clocking is enabled. When the extended control mode is enabled, this pin functions as the SDATA input. See 1.2 NORMAL/EXTENDED CONTROL for details on the extended control mode. See 1.3 THE SERIAL INTERFACE for description of the serial interface.
15	DCLK_RST	V <sub>A</sub>	DCLK Reset. A positive pulse on this pin is used to reset and synchronize the DCLK outs of multiple converters. See 1.5 MULTIPLE ADC SYNCHRONIZATION for detailed description.
26	PD	│ <del>│ </del>	Power Down Pins. A logic high on the PD pin puts the entire device into the Power Down Mode.
30	CAL	GND	Calibration Cycle Initiate. A minimum 80 input clock cycles logic low followed by a minimum of 80 input clock cycles high on this pin initiates the self calibration sequence. See 2.4.2 Self Calibration for an overview of self-calibration and 2.4.2.2 On-Command Calibration for a description of on-command calibration.
29	PDQ	V <sub>A</sub> GND	A logic high on the PDQ pin puts only the "Q" ADC into the Power Down mode.
14	FSR/ECE	50k 200k 50k 8 pF	Full Scale Range Select and Extended Control Enable. In non-extended control mode, a logic low on this pin sets the full-scale differential input range to 650 mV <sub>P-P</sub> . A logic high on this pin sets the full-scale differential input range to 870 mV <sub>P-P</sub> . See 1.1.4 The Analog Inputs. To enable the extended control mode, whereby the serial interface and control registers are employed, allow this pin to float or connect it to a voltage equal to V <sub>A</sub> /2. See 1.2 NORMAL/EXTENDED CONTROL for information on the extended control mode.

Pin No.	Symbol	Equivalent Circuit	Description
127	CalDly / DES / SCS	V <sub>A</sub> 50k 50k GND	Calibration Delay, Dual Edge Sampling and Serial Interface Chi Select. With a logic high or low on pin 14, this pin functions as Calibration Delay and sets the number of input clock cycles after power up before calibration begins (See 1.1.1 Self-Calibration). With pin 14 floating, this pin acts as the enable pin for the serial interface input and the CalDly value becomes "0" (short delay with no provision for a long power-up calibration delay). When this pis floating or connected to a voltage equal to $V_{\rm A}/2$ , DES (Dual Edge Sampling) mode is selected where the "I" input is sampled at twice the input clock rate and the "Q" input is ignored. See 1.1.5.1 Dual Edge Sampling.
18 19	CLK+ CLK-	AGND 50k VBIAS	LVDS Clock input pins for the ADC. The differential clock signal must be a.c. coupled to these pins. The input signal is sampled of the falling edge of CLK+. See 1.1.2 Acquiring the Input for a description of acquiring the input and 2.3 THE CLOCK INPUTS for an overview of the clock inputs.
11 10 22 23	V <sub>IN</sub> I+ V <sub>IN</sub> I- V <sub>IN</sub> Q+ V <sub>IN</sub> Q-	AGND V <sub>CMO</sub> 100 V <sub>CMO</sub> Control from V <sub>CM</sub> AGND	Analog signal inputs to the ADC. The differential full-scale input range of this input is programmable using the FSR pin 14 in norm mode and the Input Full-Scale Voltage Adjust register in the extended control mode. Refer to the V <sub>IN</sub> specification in the Converter Electrical Characteristics for the full-scale input range in the normal mode. Refer to 1.4 REGISTER DESCRIPTION for the full-scale input range in the extended control mode.
7	V <sub>CMO</sub>	V <sub>CMO</sub> 200k Enable AC Coupling	Common Mode Voltage. This pin is the common mode voltage output in d.c. coupling mode and also serves as the a.c. coupling mode select input. When d.c. coupling is used, the voltage output this pin is required to be the common mode input voltage at V + and V <sub>IN</sub> To select a.c. coupling at the analog input, this pin should be grounded. This pin is capable of sourcing or sinking 100µA. See 2.2 THE ANALOG INPUT.
31	V <sub>BG</sub>	VA P	Bandgap output voltage capable of 100 μA source/sink.
126	CalRun	GND	Calibration Running indication. This pin is at a logic high when calibration is running.

Pin No.	Symbol	Equivalent Circuit	Description
32	R <sub>EXT</sub>	VA GZD	External bias resistor connection. Nominal value is 3.3k-Ohms (±0.1%) to ground. See <i>1.1.1 Self-Calibration</i> .
34 35	Tdiode_P Tdiode_N	Tdiode_P O	Temperature Diode Positive (Anode) and Negative (Cathode) for die temperature measurements. See <i>2.6.2 Thermal Management</i> .

Pin Functi Pin No.	Symbol	Equivalent Circuit	Description
83 / 78	DI7- / DQ7-		·
84 / 77	DI7+ / DQ7+		
85 / 76	DI6- / DQ6-		
86 / 75	DI6+ / DQ6+		
89 / 72	DI5- / DQ5-		
90 / 71	DI5+ / DQ5+		
91 / 70	DI4- / DQ4-		I and Q channel LVDS Data Outputs that are not delayed in the
92 / 69	DI4+ / DQ4+		output demultiplexer. Compared with the DId and DQd outputs
93 / 68	DI3- / DQ3-		these outputs represent the later time samples. These outputs
94 / 67	DI3+ / DQ3+		should always be terminated with a $100\Omega$ differential resistor.
95 / 66	DI2- / DQ2-		
96 / 65	DI2+ / DQ2+		
100 / 61	DI1- / DQ1-		
101 / 60	DI1+ / DQ1+		
102 / 59	DI0- / DQ0-		
103 / 58	DI0+ / DQ0+	$V_{DR}$	
104 / 57	DId7- / DQd7-	<u> </u>	
105 / 56	Dld7+ / DQd7+	<u> </u>	
106 / 55	Dld6- / DQd6-	ΙΨΙ	
107 / 54	Dld6+ / DQd6+	. 🛨 🏪 .	
111 / 50	Dld5- / DQd5-	╌╬┰╶╬╌	
112 / 49	Dld5+ / DQd5+		
113 / 48	Dld4- / DQd4-	+	I and Q channel LVDS Data Outputs that are delayed by one C
114 / 47	Dld4+ / DQd4+		cycle in the output demultiplexer. Compared with the DI/DQ
115 / 46	Dld3- / DQd3-		outputs, these outputs represent the earlier time sample. Thes
116 / 45	Dld3+ / DQd3+	TAT	outputs should always be terminated with a $100\Omega$ differential
117 / 44	Dld2- / DQd2-	$ \Psi $	resistor.
118 / 43	Dld2+ / DQd2+	<del></del>	
122 / 39	Dld1- / DQd1-	DR GND	
123 / 38	Dld1+ / DQd1+		
124 / 37	Dld0- / DQd0-		
125 / 36	Dld0+ / DQd0+		
			Out Of Range output. A differential high at these pins indicates the
			the differential input is out of range (outside the range $\pm V_{IN}/2$ as
79	OR+		programmed by the FSR pin in non-extended control mode or t
80	OR-		Input Full-Scale Voltage Adjust register setting in the extended
			control mode).
			Differential Clock outputs used to latch the output data. Delaye
			and non-delayed data outputs are supplied synchronous to this
82	DCLK+		signal. This signal is at 1/2 the input clock rate in SDR mode at
81	DCLK-		at 1/4 the input clock rate in the DDR mode. The DCLK outputs
01	DOLK		are not active during a calibration cycle, therefore this is not
			recommended as a system clock.
2, 5, 8, 13,			
2, 5, 6, 13, 16, 17, 20,			
25, 28, 33,	V <sub>A</sub>		Analog power supply pins. Bypass these pins to ground.
128			
40, 51 ,62,	V		
73, 88, 99,	V <sub>DR</sub>		Output Driver power supply pins. Bypass these pins to DR GNI
110, 121			
1, 6, 9, 12,			
21, 24, 27,	GND		Ground return for V <sub>A</sub> .
41			

Pin Functions						
Pin No.	Symbol	Equivalent Circuit	Description			
42, 53, 64,						
74, 87, 97,	DR GND		Ground return for V <sub>DR</sub> .			
108, 119						
52, 63, 98,	NC		No Connection Make no connection to those nine			
109, 120	NC		No Connection. Make no connection to these pins.			

# **Absolute Maximum Ratings**

(Notes 2, 1)

If Military/Aerospace specified devices are required, please contact the National Semiconductor Sales Office/Distributors for availability and specifications.

Analog Supply Voltage (V<sub>A</sub>) 2.2V

Supply Difference

 $\begin{array}{ccc} {\rm V_{DR} \cdot V_{A}} & {\rm OV \ to \ 100 \ mV} \\ {\rm Driver \ Supply \ Voltage} & {\rm (V_{DR})V_{A} \ 100 \ mV)} \\ {\rm Voltage \ on \ Any \ Input \ Pin} & {\rm -0.15V \ to \ (V_{A} + 0.15V)} \end{array}$ 

**Ground Difference** 

Machine Model

IGND - DR GNDI 0V to 100 mV Input Current at Any Pin (Note 3)  $\pm 25$  mA Package Input Current (Note 3)  $\pm 50$  mA Power Dissipation at T<sub>A</sub> ≤ 85°C 2.3 W

ESD Susceptibility (Note 4)
Human Body Model 2500V

Soldering Temperature, Infrared, 10 seconds, (Note 5), (Applies to

standard plated package only)

Storage Temperature -65°C to +150°C

# Operating Ratings (Notes 1, 2)

V<sub>IN</sub>+, V<sub>IN</sub>- Voltage Range

(Maintaining Common Mode) 200mV to V<sub>A</sub>

Ground Difference

Differential CLK Amplitude 0.4V<sub>P-P</sub> to 2.0V<sub>P-P</sub>

#### **Package Thermal Resistance**

Package	$\theta_{JA}$	θ <sub>JC (Top of</sub> Package)	θ <sub>J-PAD</sub> (Thermal Pad)
128-Lead Exposed Pad LQFP	26°C / W	10°C / W	2.8°C / W

Soldering process must comply with National Semiconductor's Reflow Temperature Profile specifications. Refer to www.national.com/packaging.

# **Converter Electrical Characteristics**

The following specifications apply after calibration for  $V_A = V_{DR} = +1.9V_{DC}$ , OutV = 1.9V,  $V_{IN}$  FSR (a.c. coupled) = differential 870mV<sub>P-P</sub>,  $C_L = 10$  pF, Differential, a.c. coupled Sinewave Input Clock,  $f_{CLK} = 1.5$  GHz at 0.5V<sub>P-P</sub> with 50% duty cycle,  $V_{BG} = 1.00$  Floating, Non-Extended Control Mode, SDR Mode,  $V_{EXT} = 1.00$  Holds Signal Source Impedance = 1.00 Differential. Boldface limits apply for  $V_{EXT} = 1.00$  The sum of th

250V

235°C

Symbol	mbol Parameter Conditions		Typical (Note 8)	Limits (Note 8)	Units (Limits)
STATIC CO	NVERTER CHARACTERISTICS	•	•		
INL	Integral Non-Linearity (Best fit)	DC Coupled, 1MHz Sine Wave Overranged	±0.3	±0.9	LSB (max)
DNL	Differential Non-Linearity	DC Coupled, 1MHz Sine Wave Overranged	±0.15	±0.6	LSB (max)
	Resolution with No Missing Codes			8	Bits
V <sub>OFF</sub>	Offset Error		-0.45	-1.5 1.0	LSB (min) LSB (max)
V <sub>OFF</sub> _ADJ	Input Offset Adjustment Range	Extended Control Mode	±45		mV
PFSE	Positive Full-Scale Error	(Note 9)	-0.6	±25	mV (max)
NFSE	Negative Full-Scale Error	(Note 9)	-1.31	±25	mV (max)
FS_ADJ	Full-Scale Adjustment Range	Extended Control Mode	±20	±15	%FS
NORMAL N	ODE (Non DES) DYNAMIC CON	VERTER CHARACTERISTICS			
FPBW	Full Power Bandwidth	Normal Mode (non DES)	1.7		GHz
B.E.R.	Bit Error Rate		10-18		Error/Sample
	Cain Flatness	d.c. to 500 MHz	±0.5		dBFS
	Gain Flatness	d.c. to 1 GHz	±1.0		dBFS
ENOR	Effective Number of Dite	$f_{IN} = 373 \text{ MHz}, V_{IN} = FSR - 0.5 \text{ dB}$	7.4	7.0	Bits (min)
ENOB	Effective Number of Bits	f <sub>IN</sub> = 748 MHz, V <sub>IN</sub> = FSR – 0.5 dB	7.25		Bits (min)
OINIAD	Signal-to-Noise Plus Distortion	f <sub>IN</sub> = 373 MHz, V <sub>IN</sub> = FSR – 0.5 dB	46.3	43.9	dB (min)
SINAD	Ratio	$f_{IN} = 748 \text{ MHz}, V_{IN} = FSR - 0.5 \text{ dB}$	45.4		dB (min)
CND	Circulto Naisa Datia	f <sub>IN</sub> = 373 MHz, V <sub>IN</sub> = FSR – 0.5 dB	47	44.5	dB (min)
SNR	Signal-to-Noise Ratio	$f_{IN} = 748 \text{ MHz}, V_{IN} = FSR - 0.5 \text{ dB}$	46.3		dB (min)

Symbol	Parameter	Conditions	Typical (Note 8)	Limits (Note 8)	Units (Limits)
TUD	Tatal Hamanaia Diatastian	$f_{IN} = 373 \text{ MHz}, V_{IN} = FSR - 0.5 \text{ dB}$	-54.5	-47	dB (max)
THD	Total Harmonic Distortion	$f_{IN} = 748 \text{ MHz}, V_{IN} = FSR - 0.5 \text{ dB}$	-53		dB (max)
0 111	0 111 1 511 1	$f_{IN} = 373 \text{ MHz}, V_{IN} = \text{FSR} - 0.5 \text{ dB}$	-60		dB
2nd Harm	Second Harmonic Distortion	f <sub>IN</sub> = 748 MHz, V <sub>IN</sub> = FSR – 0.5 dB	-57		dB
		$f_{IN} = 373 \text{ MHz}, V_{IN} = \text{FSR} - 0.5 \text{ dB}$	-62		dB
3rd Harm	Third Harmonic Distortion	$f_{IN} = 748 \text{ MHz}, V_{IN} = FSR - 0.5 \text{ dB}$	-65		dB
OFFID		$f_{IN} = 373 \text{ MHz}, V_{IN} = \text{FSR} - 0.5 \text{ dB}$	56	48.5	dB (min)
SFDR	Spurious-Free dynamic Range	$f_{IN} = 748 \text{ MHz}, V_{IN} = FSR - 0.5 \text{ dB}$	53		dB (min)
IMD	Intermodulation Distortion	$f_{IN1} = 321 \text{ MHz}, V_{IN} = FSR - 7 \text{ dB}$ $f_{IN2} = 326 \text{ MHz}, V_{IN} = FSR - 7 \text{ dB}$	-50		dB
	Out of Range Output Code	$(V_{IN}^+) - (V_{IN}^-) > + \text{Full Scale}$		255	
	(In addition to OR Output high)	$(V_{IN}^+) - (V_{IN}^-) < -$ Full Scale		0	
INTERLEAV		DYNAMIC CONVERTER CHARACTERI	STICS		
FPBW					
(DES)	Full Power Bandwidth	Dual Edge Sampling Mode	900		MHz
ENOB	Effective Number of Bits	$f_{IN} = 748 \text{ MHz}, V_{IN} = FSR - 0.5 \text{ dB}$	7.2		Bits (min)
SINAD	Signal to Noise Plus Distortion Ratio	f <sub>IN</sub> = 748 MHz, V <sub>IN</sub> = FSR – 0.5 dB	45		dB (min)
SNR	Signal to Noise Ratio	$f_{IN} = 748 \text{ MHz}, V_{IN} = FSR - 0.5 \text{ dB}$	45.5		dB (min)
THD	Total Harmonic Distortion	$f_{IN} = 748 \text{ MHz}, V_{IN} = FSR - 0.5 \text{ dB}$	-53.5		dB (max)
2nd Harm	Second Harmonic Distortion	f <sub>IN</sub> = 748 MHz, V <sub>IN</sub> = FSR - 0.5 dB	-54		dB
3rd Harm	Third Harmonic Distortion	f <sub>IN</sub> = 748 MHz, V <sub>IN</sub> = FSR – 0.5 dB	-64		dB
SFDR	Spurious Free Dynamic Range	f <sub>IN</sub> = 748 MHz, V <sub>IN</sub> = FSR - 0.5 dB	53.4		dB (min)
ANALOG IN	IPUT AND REFERENCE CHARA		1		, ,
				570	mV <sub>P-P</sub> (min
	Full Scale Analog Differential Input Range	FSR pin 14 Low	650	730	mV <sub>P-P</sub> (max
$V_{IN}$				790	mV <sub>P-P</sub> (min
		FSR pin 14 High	870	950	mV <sub>P-P</sub> (max
			+	+	mV (min)
V <sub>CMI</sub>	Analog Input Common Mode		V <sub>CMO</sub>	V <sub>CMO</sub> - 50	, ,
V <sub>CMI</sub>	Voltage		V <sub>CMO</sub>	V <sub>CMO</sub> - 50 V <sub>CMO</sub> + 50	mV (max)
V <sub>CMI</sub>	Voltage Analog Input Capacitance,	Differential	V <sub>CMO</sub> 0.02		, ,
	Voltage Analog Input Capacitance, Normal operation (Notes 11, 10)	Each input pin to ground	0.02		mV (max) pF pF
	Voltage  Analog Input Capacitance, Normal operation (Notes 11, 10)  Analog Input Capacitance,	Each input pin to ground Differential	0.02 1.6 0.08		mV (max) pF pF
	Voltage Analog Input Capacitance, Normal operation (Notes 11, 10)	Each input pin to ground	0.02	V <sub>CMO</sub> + 50	mV (max) pF pF pF
C <sub>IN</sub>	Voltage  Analog Input Capacitance, Normal operation (Notes 11, 10)  Analog Input Capacitance,	Each input pin to ground Differential	0.02 1.6 0.08	V <sub>CMO</sub> + 50	mV (max) pF pF pF pF pC (min)
C <sub>IN</sub>	Voltage  Analog Input Capacitance, Normal operation (Notes 11, 10)  Analog Input Capacitance, DES Mode (Notes 10, 11)  Differential Input Resistance	Each input pin to ground Differential	0.02 1.6 0.08 2.2	V <sub>CMO</sub> + 50	mV (max) pF pF pF
C <sub>IN</sub>	Voltage Analog Input Capacitance, Normal operation (Notes 11, 10) Analog Input Capacitance, DES Mode (Notes 10, 11)	Each input pin to ground Differential	0.02 1.6 0.08 2.2	94 106	mV (max) pF pF pF pF Ω (min) Ω (max)
C <sub>IN</sub> R <sub>IN</sub> ANALOG O	Voltage  Analog Input Capacitance, Normal operation (Notes 11, 10)  Analog Input Capacitance, DES Mode (Notes 10, 11)  Differential Input Resistance  UTPUT CHARACTERISTICS  Common Mode Output Voltage	Each input pin to ground Differential	0.02 1.6 0.08 2.2	V <sub>CMO</sub> + 50	mV (max) pF pF pF pF Ω (min)
C <sub>IN</sub> R <sub>IN</sub> ANALOG O	Voltage  Analog Input Capacitance, Normal operation (Notes 11, 10)  Analog Input Capacitance, DES Mode (Notes 10, 11)  Differential Input Resistance  UTPUT CHARACTERISTICS	Each input pin to ground  Differential  Each input pin to ground	0.02 1.6 0.08 2.2 100	94 106	mV (max) pF pF pF pF Ω (min) Ω (max)
C <sub>IN</sub> R <sub>IN</sub> ANALOG O  V <sub>CMO</sub> TC V <sub>CMO</sub>	Voltage  Analog Input Capacitance, Normal operation (Notes 11, 10)  Analog Input Capacitance, DES Mode (Notes 10, 11)  Differential Input Resistance  UTPUT CHARACTERISTICS  Common Mode Output Voltage  Common Mode Output Voltage	Each input pin to ground  Differential Each input pin to ground $I_{CMO} = \pm 100 \ \mu A$ $T_A = -40^{\circ}C \ to +85^{\circ}C$ $V_A = 1.8V$	0.02 1.6 0.08 2.2 100	94 106	mV (max) pF pF pF pC (min) Ω (max) V (min) V (max)
C <sub>IN</sub> R <sub>IN</sub> ANALOG O  V <sub>CMO</sub> TC V <sub>CMO</sub>	Voltage  Analog Input Capacitance, Normal operation (Notes 11, 10)  Analog Input Capacitance, DES Mode (Notes 10, 11)  Differential Input Resistance  UTPUT CHARACTERISTICS  Common Mode Output Voltage Common Mode Output Voltage Temperature Coefficient	Each input pin to ground   Differential   Each input pin to ground $I_{CMO} = \pm 100 \ \mu A$ $T_A = -40^{\circ}C \ to \ +85^{\circ}C$	0.02 1.6 0.08 2.2 100 1.26	94 106	mV (max) pF pF pF pF Ω (min) Ω (max) V (min) V (max) ppm/°C
V <sub>CMI</sub> C <sub>IN</sub> R <sub>IN</sub> ANALOG O  V <sub>CMO</sub> TC V <sub>CMO</sub> V <sub>CMO_LVL</sub> C <sub>LOAD</sub> V <sub>CMO</sub>	Voltage  Analog Input Capacitance, Normal operation (Notes 11, 10)  Analog Input Capacitance, DES Mode (Notes 10, 11)  Differential Input Resistance  UTPUT CHARACTERISTICS  Common Mode Output Voltage Common Mode Output Voltage Temperature Coefficient  V <sub>CMO</sub> input threshold to set DC Coupling mode	Each input pin to ground  Differential Each input pin to ground $I_{CMO} = \pm 100 \ \mu A$ $T_A = -40^{\circ}C \ to +85^{\circ}C$ $V_A = 1.8V$	0.02 1.6 0.08 2.2 100 1.26 118 0.60	94 106	mV (max) pF pF pF pF Ω (min) Ω (max) V (min) V (max) ppm/°C

9

Symbol	Parameter	Conditions	Typical (Note 8)	Limits (Note 8)	Units (Limits)
TC V <sub>BG</sub>	Bandgap Reference Voltage Temperature Coefficient	$T_A = -40^{\circ}\text{C to } +85^{\circ}\text{C},$ $I_{BG} = \pm 100 \ \mu\text{A}$	28		ppm/°C
C <sub>LOAD</sub> V <sub>BG</sub>	Maximum Bandgap Reference load Capacitance			80	pF
TEMPERAT	TURE DIODE CHARACTERISTICS				
		192 μA vs. 12 μA, Τ <sub>J</sub> = 25°C	71.23		mV
$\Delta V_{BE}$	Temperature Diode Voltage	192 μA vs. 12 μA, Τ <sub>J</sub> = 85°C	85.54		mV
CHANNEL-	TO-CHANNEL CHARACTERISTIC	<u> </u>		1	
	Offset Match		1		LSB
	Positive Full-Scale Match	Zero offset selected in Control Register	1		LSB
	Negative Full-Scale Match	Zero offset selected in Control Register	1		LSB
	Phase Matching (I, F.S.Q)	F <sub>IN</sub> = 1.0 GHz	< 1		Degree
	Crosstalk from I (Aggressor) to Q	" '			
X-TALK	(Victim) Channel	Victim = 100 MHz F.S.	-71		dB
X-TALK	Crosstalk from Q (Aggressor) to I (Victim) Channel	rom Q (Aggressor) to I Aggressor = 867 MHz F.S.			dB
CLOCK INF	PUT CHARACTERISTICS	1			
		Sine Wave Clock	0.6	0.4	V <sub>P-P</sub> (min)
$V_{ID}$		Square Wave Clock	0.6	2.0 0.4 2.0	V <sub>P-P</sub> (max) V <sub>P-P</sub> (min) V <sub>P-P</sub> (max)
I <sub>I</sub>	Input Current	$V_{IN} = 0$ or $V_{IN} = V_A$	±1	2.0	μ <b>A</b>
'	•	Differential	0.02		pF
C <sub>IN</sub>	Input Capacitance (Notes 10, 11)	Each input to ground	1.5		pF
DIGITAL CO	ONTROL PIN CHARACTERISTICS		1.5	1	рі
V <sub>IH</sub>	Logic High Input Voltage	(Note 12)		0.85 x V <sub>A</sub>	V (min)
	<del>                                     </del>	·		0.05 X V <sub>A</sub>	` '
V <sub>IL</sub> C <sub>IN</sub>	Logic Low Input Voltage Input Capacitance	(Note 12)  Each input to ground	1.2	0.15 X V <sub>A</sub>	V (max) pF
○ <sub>IN</sub>	(Notes 11, 13)	Lacii inpat to ground	1.2		Ρı
DIGITAL O	UTPUT CHARACTERISTICS				
		Measured differentially, $OutV = V_A$ , $V_{BG}$	710	400	mV <sub>P-P</sub> (min
V	LVDS Differential Output Voltage	= Floating (Note 15)	710	920	mV <sub>P-P</sub> (max
V <sub>OD</sub>	LVDS Dillerential Output Voltage	Measured differentially, OutV = GND,	F10	280	mV <sub>P-P</sub> (min
		V <sub>BG</sub> = Floating (Note 15)	510	720	mV <sub>P-P</sub> (max
Δ V <sub>O DIFF</sub>	Change in LVDS Output Swing Between Logic Levels		±1		mV
V <sub>OS</sub>	Output Offset Voltage, see Figure 1	V <sub>BG</sub> = Floating	800		mV
V <sub>OS</sub>	Output Offset Voltage, see Figure 1	V <sub>BG</sub> = V <sub>A</sub> (Note 15)	1200		mV
Δ V <sub>OS</sub>	Output Offset Voltage Change Between Logic Levels		±1		mV
I <sub>os</sub>	Output Short Circuit Current	Output+ & Output- connected to 0.8V	±4		mA
Z <sub>O</sub>	Differential Output Impedance		100		Ohms
V <sub>OH</sub>	CalRun High level output	I <sub>OH</sub> = -400uA (Note 12)	1.65	1.5	V
V <sub>OL</sub>	CalRun Low High level output	I <sub>OH</sub> = 400uA (Note 12)	0.15	0.3	V

Symbol	Parameter	Conditions		Typical (Note 8)	Limits (Note 8)	Units (Limits)
POWER SU	PPLY CHARACTERISTICS					
		PD = PDQ = Low		770	870	mA (max)
I <sub>A</sub>	Analog Supply Current	PD = Low, PDQ = High		524	600	mA (max)
		PD = PDQ = High		1.8		mA
		PD = PDQ = Low		207	290	mA (max)
I <sub>DR</sub>	Output Driver Supply Current	PD = Low, PDQ = H	igh	116	165	mA (max)
		PD = PDQ = High		0.012		mA
_		PD = PDQ = Low		1.8	2.2	W (max)
$P_{D}$	Power Consumption	PD = Low, PDQ = H	igh	1.2	1.45	W (max)
		PD = PDQ = High	. Fanon militar ale anno	3.5		mW
PSRR1	D.C. Power Supply Rejection Ratio	Change in Full Scale in V <sub>A</sub> from 1.8V to 2.	-	30		dB
PSRR2	A.C. Power Supply Rejection Ratio	248 MHz, 50mV <sub>P-P</sub> r	iding on V <sub>A</sub>	51		dB
AC ELECTF	RICAL CHARACTERISTICS					
f <sub>CLK1</sub>	Maximum Input Clock Frequency	Normal Mode (non D	DES) or DES Mode	1.7	1.5	GHz (min)
f <sub>CLK2</sub>	Minimum Input Clock Frequency	Normal Mode (non E		200		MHz
f <sub>CLK2</sub>	Minimum Input Clock Frequency	DES Mode	- /	500		MHz
CLK2	William input clock i requeries		-1. f	000	20	
	Input Clock Duty Cycle	200 MHz ≤ Input clock frequency ≤ 1.5 GHz <b>(Normal Mode)</b> (Note 12)		50	80	% (min) % (max)
	Input Clock Duty Cycle	500MHz ≤ Input clock frequency ≤ 1.5 GHz ( <b>DES Mode</b> ) (Note 12)		50	20 80	% (min) % (max)
t <sub>CL</sub>	Input Clock Low Time	(Note 11)	,	333	133	ps (min)
t <sub>ch</sub>	Input Clock High Time	(Note 11)		333	133	ps (min)
СП	DCLK Duty Cycle	(Note 11)		50	45 55	% (min) % (max)
+	Reset Setup Time	(Note 11)		150	33	
t <sub>RS</sub>	•					ps
t <sub>RH</sub>	Reset Hold Time	(Note 11)		250		ps
t <sub>SD</sub>	Synchronizing Edge to DCLK Output Delay			t <sub>OD</sub> + t <sub>OSK</sub>		
t <sub>RPW</sub>	Reset Pulse Width	(Note 11)			4	Clock Cycles (min)
t <sub>LHT</sub>	Differential Low to High Transition Time	10% to 90%, $C_L = 2$ .	5 pF	250		ps
t <sub>HLT</sub>	Differential High to Low Transition Time	10% to 90%, C <sub>L</sub> = 2.	5 pF	250		ps
t <sub>osk</sub>	DCLK to Data Output Skew	50% of DCLK transit transition, SDR Mod and DDR Mode, 0° [	e	±50		ps (max)
t <sub>su</sub>	Data to DCLK Set-Up Time	DDR Mode, 90° DCI	_K (Note 11)	400		ns
t <sub>H</sub>	DCLK to Data Hold Time	DDR Mode, 90° DCI	_K (Note 11)	560		ns
t <sub>AD</sub>	Sampling (Aperture) Delay	Input CLK+ Fall to A	` ′	1.3		ns
t <sub>AJ</sub>	Aperture Jitter		•	0.4		ps rms
	Input Clock to Data Output Delay	50% of Input Clock t	ransition to 50% of			F
t <sub>od</sub>	(in addition to Pipeline Delay)	Data transition		3.1		ns
		DI Outputs			13	
		Dld Outputs			14	
	Pipeline Delay (Latency)	DQ Outputs	Normal Mode		13	Input Clock
	(Notes 11, 14)	_ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~	DES Mode		13.5	Cycles
		DQd Outputs	Normal Mode		14	
	i e	Daa Garbara	DES Mode		14.5	I

Symbol	Parameter	Conditions	Typical (Note 8)	Limits (Note 8)	Units (Limits)
	Over Range Recovery Time	Differential V <sub>IN</sub> step from ±1.2V to 0V to get accurate conversion	1		Input Clock Cycle
t <sub>WU</sub>	PD low to Rated Accuracy Conversion (Wake-Up Time)		500		ns
	DCS	(Note 11)	1		μs
f <sub>SCLK</sub>	Serial Clock Frequency	(Note 11)	100		MHz
t <sub>SSU</sub>	Data to Serial Clock Setup Time	(Note 11)	2.5		ns (min)
t <sub>SH</sub>	Data to Serial Clock Hold Time	(Note 11)	1		ns (min)
	Serial Clock Low Time			4	ns (min)
	Serial Clock High Time			4	ns (min)
t <sub>CAL</sub>	Calibration Cycle Time		1.4 x 10 <sup>5</sup>		Clock Cycles
t <sub>CAL_L</sub>	CAL Pin Low Time	See Figure 9 (Note 11)		80	Clock Cycles (min)
t <sub>CAL_H</sub>	CAL Pin High Time	See Figure 9(Note 11)		80	Clock Cycles (min)
+	Calibration delay determined by	CalDly = Low See 1.1.1 Self-Calibration, Figure 9, (Note 11)		<b>2</b> <sup>25</sup>	Clock Cycles (min)
t <sub>CalDly</sub>	pin 127	CalDly = High See 1.1.1 Self-Calibration, Figure 9, (Note 11)		231	Clock Cycles (max)

**Note 1:** Absolute Maximum Ratings indicate limits beyond which damage to the device may occur. There is no guarantee of operation at the Absolute Maximum Ratings. Operating Ratings indicate conditions for which the device is functional, but do not guarantee specific performance limits. For guaranteed specifications and test conditions, see the Electrical Characteristics. The guaranteed specifications apply only for the test conditions listed. Some performance characteristics may degrade when the device is not operated under the listed test conditions.


Note 2: All voltages are measured with respect to GND = DR GND = 0V, unless otherwise specified.

**Note 3:** When the input voltage at any pin exceeds the power supply limits (that is, less than GND or greater than  $V_A$ ), the current at that pin should be limited to 25 mA. The 50 mA maximum package input current rating limits the number of pins that can safely exceed the power supplies with an input current of 25 mA to two. This limit is not placed upon the power, ground and digital output pins.

Note 4: Human body model is 100 pF capacitor discharged through a 1.5 kΩ resistor. Machine model is 220 pF discharged through ZERO Ohms.

 $\textbf{Note 5:} \ \textbf{See AN-450}, \ \textbf{``Surface Mounting Methods and Their Effect on Product Reliability''}.$ 

Note 6: The analog inputs are protected as shown below. Input voltage magnitudes beyond the Absolute Maximum Ratings may damage this device.



Note 7: To guarantee accuracy, it is required that  $V_A$  and  $V_{DR}$  be well bypassed. Each supply pin must be decoupled with separate bypass capacitors. Additionally, achieving rated performance requires that the backside exposed pad be well grounded.

Note 8: Typical figures are at T<sub>A</sub> = 25°C, and represent most likely parametric norms. Test limits are guaranteed to National's AOQL (Average Outgoing Quality Level).

**Note 9:** Calculation of Full-Scale Error for this device assumes that the actual reference voltage is exactly its nominal value. Full-Scale Error for this device, therefore, is a combination of Full-Scale Error and Reference Voltage Error. See *Figure 2*. For relationship between Gain Error and Full-Scale Error, see Specification Definitions for Gain Error.

Note 10: The analog and clock input capacitances are die capacitances only. Additional package capacitances of 0.65 pF differential and 0.95 pF each pin to ground are isolated from the die capacitances by lead and bond wire inductances.

Note 11: This parameter is guaranteed by design and is not tested in production.

Note 12: This parameter is guaranteed by design and/or characterization and is not tested in production.

Note 13: The digital control pin capacitances are die capacitances only. Additional package capacitance of 1.6 pF each pin to ground are isolated from the die capacitances by lead and bond wire inductances.

Note 14: Each of the two converters of the ADC08D1500 has two LVDS output buses, which each clock data out at one half the sample rate. The data at each bus is clocked out at one half the sample rate. The second bus (D0 through D7) has a pipeline latency that is one Input Clock cycle less than the latency of the first bus (Dd0 through Dd7).

Note 15: Tying  $V_{BG}$  to the supply rail will increase the output offset voltage  $(V_{OS})$  by 400mv (typical), as shown in the  $V_{OS}$  specification above. Tying  $V_{BG}$  to the supply rail will also affect the differential LVDS output voltage  $(V_{OD})$ , causing it to increase by 40mV (typical).

# **Specification Definitions**

**APERTURE (SAMPLING) DELAY** is the amount of delay, measured from the sampling edge of the CLK input, after which the signal present at the input pin is sampled inside the device.

**APERTURE JITTER** (t<sub>AJ</sub>) is the sample to sample variation in aperture delay. Aperture jitter shows up as input noise.

**CODE ERROR RATE (C.E.R.)** is the probability of error and is defined as the probable number of word errors on the ADC output per unit of time divided by the number of words seen in that amount of time. A C.E.R. of 10<sup>-18</sup> corresponds to a statistical error in one word about every four (4) years.

**CLOCK DUTY CYCLE** is the ratio of the time that the clock wave form is at a logic high to the clock period.

**DIFFERENTIAL NON-LINEARITY (DNL)** is the measure of the maximum deviation from the ideal step size of 1 LSB. Measured at sample rate = 1500 MSPS with a 1MHz input sinewaye.

**EFFECTIVE NUMBER OF BITS (ENOB, or EFFECTIVE BITS)** is another method of specifying Signal-to-Noise and Distortion Ratio, or SINAD. ENOB is defined as (SINAD – 1.76) / 6.02 and says that the converter is equivalent to a perfect ADC of this (ENOB) number of bits.

**FULL POWER BANDWIDTH (FPBW)** is a measure of the frequency at which the reconstructed output fundamental drops 3 dB below its low frequency value for a full scale input.

**GAIN ERROR** is the deviation from the ideal slope of the transfer function. It can be calculated from Offset and Full-Scale Errors:

Pos. Gain Error = Offset Error – Pos. Full-Scale Error Neg. Gain Error = –(Offset Error – Neg. Full-Scale Error) Gain Error = Neg. Full-Scale Error – Pos. Full-Scale Error = Pos. Gain Error + Neg. Gain Error

**INTEGRAL NON-LINEARITY (INL)** is a measure of worst case deviation of the ADC transfer function from an ideal straight line drawn through the ADC transfer function. The deviation of any given code from this straight line is measured from the center of that code value step. The best fit method is used.

**INTERMODULATION DISTORTION (IMD)** is the creation of additional spectral components as a result of two sinusoidal frequencies being applied to the ADC input at the same time. It is defined as the ratio of the power in the second and third order intermodulation products to the power in one of the original frequencies. IMD is usually expressed in dBFS.

**LSB (LEAST SIGNIFICANT BIT)** is the bit that has the smallest value or weight of all bits. This value is

$$V_{ES} / 2^n$$

where  $V_{FS}$  is the differential full-scale amplitude  $V_{IN}$  as set by the FSR input and "n" is the ADC resolution in bits, which is 8 for the ADC08D1500.

**LVDS DIFFERENTIAL OUTPUT VOLTAGE (V\_{OD})** is the absolute value of the difference between the  $V_D+$  &  $V_D$ - outputs; each measured with respect to Ground.




FIGURE 1.

**LVDS OUTPUT OFFSET VOLTAGE** ( $V_{OS}$ ) is the midpoint between the D+ and D- pins output voltage with respect to ground; i.e.,  $[(V_D+) + (V_D-)]/2$ .

**MISSING CODES** are those output codes that are skipped and will never appear at the ADC outputs. These codes cannot be reached with any input value.

**MSB (MOST SIGNIFICANT BIT)** is the bit that has the largest value or weight. Its value is one half of full scale.

**NEGATIVE FULL-SCALE ERROR (NFSE)** is a measure of how far the first code transition is from the ideal 1/2 LSB above a differential -V<sub>IN</sub>/2. For the ADC08D1500 the reference voltage is assumed to be ideal, so this error is a combination of full-scale error and reference voltage error.

**OFFSET ERROR (V\_{OFF})** is a measure of how far the midscale point is from the ideal zero voltage differential input. Offset Error = Actual Input causing average of 8k samples to result in an average code of 127.5.

**OUTPUT DELAY**  $(t_{OD})$  is the time delay (in addition to Pipeline Delay) after the falling edge of CLK+ before the data update is present at the output pins.

**OVER-RANGE RECOVERY TIME** is the time required after the differential input voltages goes from ±1.2V to 0V for the converter to recover and make a conversion with its rated accuracy.

**PIPELINE DELAY (LATENCY)** is the number of input clock cycles between initiation of conversion and when that data is presented to the output driver stage. New data is available at every clock cycle, but the data lags the conversion by the Pipeline Delay plus the  $t_{\rm OD}$ .

**POSITIVE FULL-SCALE ERROR (PFSE)** is a measure of how far the last code transition is from the ideal 1-1/2 LSB below a differential  $+V_{\rm IN}/2$ . For the ADC08D1500 the reference voltage is assumed to be ideal, so this error is a combination of full-scale error and reference voltage error.

**POWER SUPPLY REJECTION RATIO (PSRR)** can be one of two specifications. PSRR1 (DC PSRR) is the ratio of the change in full-scale error that results from a power supply voltage change from 1.8V to 2.0V. PSRR2 (AC PSRR) is a measure of how well an a.c. signal riding upon the power supply is rejected from the output and is measured with a 248 MHz, 50 mV<sub>P-P</sub> signal riding upon the power supply. It is the ratio of the output amplitude of that signal at the output to its amplitude on the power supply pin. PSRR is expressed in dB.

**SIGNAL TO NOISE RATIO (SNR)** is the ratio, expressed in dB, of the rms value of the input signal at the output to the rms value of the sum of all other spectral components below one-half the sampling frequency, not including harmonics or d.c.

SIGNAL TO NOISE PLUS DISTORTION (S/(N+D) or SINAD) is the ratio, expressed in dB, of the rms value of the input signal at the output to the rms value of all of the other spectral components below half the input clock frequency, including harmonics but excluding d.c.

**SPURIOUS-FREE DYNAMIC RANGE (SFDR)** is the difference, expressed in dB, between the rms values of the input signal at the output and the peak spurious signal, where a spurious signal is any signal present in the output spectrum that is not present at the input, excluding d.c.

**TOTAL HARMONIC DISTORTION (THD)** is the ratio expressed in dB, of the rms total of the first nine harmonic levels at the output to the level of the fundamental at the output. THD is calculated as

THD = 20 x log 
$$\sqrt{\frac{A_{f2}^2 + ... + A_{f10}^2}{A_{f1}^2}}$$

where  $A_{f1}$  is the RMS power of the fundamental (output) frequency and  $A_{f2}$  through  $A_{f10}$  are the RMS power of the first 9 harmonic frequencies in the output spectrum.

- Second Harmonic Distortion (2nd Harm) is the difference, expressed in dB, between the RMS power in the input frequency seen at the output and the power in its 2nd harmonic level at the output.
- Third Harmonic Distortion (3rd Harm) is the difference expressed in dB between the RMS power in the input frequency seen at the output and the power in its 3rd harmonic level at the output.

# **Transfer Characteristic**




FIGURE 2. Input / Output Transfer Characteristic

# **Timing Diagrams**




FIGURE 3. ADC08D1500 Timing — SDR Clocking





FIGURE 4. ADC08D1500 Timing — DDR Clocking



**FIGURE 5. Serial Interface Timing** 




FIGURE 6. Clock Reset Timing in DDR Mode




FIGURE 7. Clock Reset Timing in SDR Mode with OUTEDGE Low




FIGURE 8. Clock Reset Timing in SDR Mode with OUTEDGE High





FIGURE 9. Self Calibration and On-Command Calibration Timing

17

# **Typical Performance Characteristics** $V_A = V_{DR} = 1.9V$ , $F_{CLK} = 1500 MHz$ , $T_A = 25 ^{\circ}C$ unless otherwise stated.



1.0

0.8

0.4


0.2

0.0 -0.2 -0.4

-0.6 -0.8 -1.0

0

DNL (LSB)




20152166


255

#### **POWER CONSUMPTION vs. SAMPLE RATE**

**OUTPUT CODE** 









20152165

## DNL vs. TEMPERATURE




20152167

#### **ENOB vs. TEMPERATURE**



20152176

#### **ENOB vs. SUPPLY VOLTAGE**




#### 20152177


# 7.8 7.0 0 400 800 1200 1600 CLOCK FREQUENCY (MHz)

#### 20152178

#### **ENOB vs. INPUT FREQUENCY**




20152179




20152168


#### **SNR vs. SUPPLY VOLTAGE**




20152169




20152170






-50 -52


THD vs. SUPPLY VOLTAGE






THD vs. INPUT FREQUENCY -40 -45 -55 -60 400 1200 1600 INPUT FREQUENCY (MHZ) 20152175

20152173







#### SFDR (DB) CLOCK FREQUENCY (MHz)


SFDR vs. SAMPLE RATE

SFDR vs. INPUT FREQUENCY







Spectral Response at FIN = 745 MHz



CROSSTALK vs. SOURCE FREQUENCY





# 1.0 Functional Description

The ADC08D1500 is a versatile A/D Converter with an innovative architecture permitting very high speed operation. The controls available ease the application of the device to circuit solutions. Optimum performance requires adherence to the provisions discussed here and in the Applications Information Section.

While it is generally poor practice to allow an active pin to float, pins 4, 14 and 127 of the ADC08D1500 are designed to be left floating without jeopardy. In all discussions throughout this data sheet, whenever a function is called by allowing a control pin to float, connecting that pin to a potential of one half the  $V_A$  supply voltage will have the same effect as allowing it to float.

#### 1.1 OVERVIEW

The ADC08D1500 uses a calibrated folding and interpolating architecture that achieves 7.4 effective bits. The use of folding amplifiers greatly reduces the number of comparators and power consumption. Interpolation reduces the number of front-end amplifiers required, minimizing the load on the input signal and further reducing power requirements. In addition to other things, on-chip calibration reduces the INL bow often seen with folding architectures. The result is an extremely fast, high performance, low power converter.

The analog input signal that is within the converter's input voltage range is digitized to eight bits at speeds of 200 MSPS to 1.7 GSPS, typical. Differential input voltages below negative full-scale will cause the output word to consist of all zeroes. Differential input voltages above positive full-scale will cause the output word to consist of all ones. Either of these conditions at either the "I" or "Q" input will cause the OR (Out of Range) output to be activated. This single OR output indicates when the output code from one or both of the channels is below negative full scale or above positive full scale.

Each of the two converters has a 1:2 demultiplexer that feeds two LVDS output buses. The data on these buses provide an output word rate on each bus at half the ADC sampling rate and must be interleaved by the user to provide output words at the full conversion rate.

The output levels may be selected to be normal or reduced. Using reduced levels saves power but could result in erroneous data capture of some or all of the bits, especially at higher sample rates and in marginally designed systems.

#### 1.1.1 Self-Calibration

A self-calibration is performed upon power-up and can also be invoked by the user upon command. Calibration trims the  $100\Omega$  analog input differential termination resistor and minimizes full-scale error, offset error, DNL and INL, resulting in maximizing SNR, THD, SINAD (SNDR) and ENOB. Internal bias currents are also set with the calibration process. All of this is true whether the calibration is performed upon power up or is performed upon command. Running the self calibration is an important part of this chip's functionality and is required in order to obtain adequate performance. In addition to the requirement to be run at power-up, self calibration must be re-run whenever the sense of the FSR pin is changed. For best performance, we recommend that self calibration be run 20 seconds or more after application of power and whenever the operating temperature changes significantly relative to the specific system performance requirements. See 2.4.2.2 On-Command Calibration for more information. Calibration can not be initiated or run while the device is in the power-down mode. See 1.1.7 Power Down for information on the interaction between Power Down and Calibration.

During the calibration process, the input termination resistor is trimmed to a value that is equal to  $R_{\text{EXT}}$  / 33. This external resistor is located between pin 32 and ground.  $R_{\text{EXT}}$  must be 3300  $\Omega$  ±0.1%. With this value, the input termination resistor is trimmed to be 100  $\Omega$ . Because  $R_{\text{EXT}}$  is also used to set the proper current for the Track and Hold amplifier, for the preamplifiers and for the comparators, other values of  $R_{\text{EXT}}$  should not be used

In normal operation, calibration is performed just after application of power and whenever a valid calibration command is given, which is holding the CAL pin low for at least  $t_{\text{CAL\_L}}$  clock cycles, then hold it high for at least another  $t_{\text{CAL\_H}}$  clock cycles as defined in the Converter Electrical Characteristics. The time taken by the calibration procedure is specified as  $t_{\text{CAL}}$  in Converter Electrical Characteristics. Holding the CAL pin high upon power up will prevent the calibration process from running until the CAL pin experiences the above-mentioned  $t_{\text{CAL\_L}}$  clock cycles followed by  $t_{\text{CAL\_H}}$  clock cycles.

CalDly (pin 127) is used to select one of two delay times after the application of power to the start of calibration. This calibration delay time is depedent on the setting of the CalDly pin and is specified as  $t_{\text{CalDly}}$  in the Converter Electrical Characteristics. These delay values allow the power supply to come up and stabilize before calibration takes place. If the PD pin is high upon power-up, the calibration delay counter will be disabled until the PD pin is brought low. Therefore, holding the PD pin high during power up will further delay the start of the power-up calibration cycle. The best setting of the CalDly pin depends upon the power-on settling time of the power supply.

#### **Calibration Operation Notes:**

- During the calibration cycle, the OR output may be active as a result of the calibration algorithm. All data on the output pins and the OR output are invalid during the calibration cycle.
- During the power-up calibration and during the oncommand calibration, all clocks are halted on chip, including internal clocks and DCLK, while the input termination resistor is trimmed to a value that is equal to R<sub>EXT</sub> / 33. This is to reduce noise during the input resistor calibration portion of the calibration cycle. See 2.4.2 Self Calibration.
  - This external resistor is located between pin 32 and ground.  $R_{EXT}$  must be 3300  $\Omega$  ±0.1%. With this value, the input termination resistor is trimmed to be 100  $\Omega.$  Because  $R_{EXT}$  is also used to set the proper current for the Track and Hold amplifier, for the preamplifiers and for the comparators, other values of  $R_{EXT}$  should not be used.
- The CalRun output is high whenever the calibration procedure is running. This is true whether the calibration is done at power-up or on-command.

#### 1.1.2 Acquiring the Input

Data is acquired at the falling edge of CLK+ (pin 18) and the digital equivalent of that data is available at the digital outputs 13 input clock cycles later for the DI and DQ output buses and 14 input clock cycles later for the DId and DQd output buses. There is an additional internal delay called  $t_{\rm OD}$  before the data is available at the outputs. See the Timing Diagram. The ADC08D1500 will convert as long as the input clock signal is present. The fully differential comparator design and the innovative design of the sample-and-hold amplifier, together with self calibration, enables a very flat SINAD/ENOB response beyond 1.5 GHz. The ADC08D1500 output data signaling is LVDS and the output format is offset binary.

#### 1.1.3 Control Modes

Much of the user control can be accomplished with several control pins that are provided. Examples include initiation of the calibration cycle, power down mode and full scale range setting. However, the ADC08D1500 also provides an Extended Control mode whereby a serial interface is used to access register-based control of several advanced features. The Extended Control mode is not intended to be enabled and disabled dynamically. Rather, the user is expected to employ either the normal control mode or the Extended Control mode at all times. When the device is in the Extended Control mode, pin-based control of several features is replaced with register-based control and those pin-based controls are disabled. These pins are OutV (pin 3), OutEdge/DDR (pin 4), FSR (pin 14) and CalDly/DES (pin 127). See 1.2 NORMAL/EXTEND-ED CONTROL for details on the Extended Control mode.

#### 1.1.4 The Analog Inputs

The ADC08D1500 must be driven with a differential input signal. Operation with a single-ended signal is not recommended. It is important that the inputs either be a.c. coupled to the inputs with the  $\rm V_{CMO}$  pin grounded, or d.c. coupled with the  $\rm V_{CMO}$  pin left floating. An input common mode voltage equal to the  $\rm V_{CMO}$  output must be provided when d.c. coupling is used.

Two full-scale range settings are provided with pin 14 (FSR). The input full-scale range is programmable in the normal mode by setting a level on pin 14 (FSR) as defined in by the specification  $V_{\rm IN}$  in the Converter Electrical Characteristics. The full-scale range setting operates equally on both ADCs. In the Extended Control mode, programming the Input Full-Scale Voltage Adjust register allows the input full-scale range to be adjusted as described in 1.4 REGISTER DESCRIPTION and 2.2 THE ANALOG INPUT.

#### 1.1.5 Clocking

The ADC08D1500 must be driven with an a.c. coupled, differential clock signal. 2.3 THE CLOCK INPUTS describes the use of the clock input pins. A differential LVDS output clock is available for use in latching the ADC output data into whatever device is used to receive the data.

The ADC08D1500 offers two options for output clocking. These options include a choice of which DCLK edge the out-

put data transitions on and a choice of Single Data Rate (SDR) or Double Data Rate (DDR) outputs.

The ADC08D1500 also has the option to use a duty cycle corrected clock receiver as part of the input clock circuit. This feature is enabled by default and provides improved ADC clocking. This circuitry allows the ADC to be clocked with a signal source having a duty cycle ratio of 80 / 20 % (worst case).

#### 1.1.5.1 Dual-Edge Sampling

The DES mode allows one of the ADC08D1500's inputs (I or Q Channel) to be sampled by both ADCs. One ADC samples the input on the positive edge of the input clock and the other ADC samples the same input on the other edge of the input clock. A single input is thus sampled twice per input clock cycle, resulting in an overall sample rate of twice the input clock frequency, or 3 GSPS with a 1.5 GHz input clock.

In this mode the outputs are interleaved such that the data is effectively demultiplexed 1:4. Since the sample rate is doubled, each of the 4 output buses have a 750 MHz output rate with a 1.5 GHz input clock. All data is available in parallel. The four bytes of parallel data that are output with each clock is in the following sampling order, from the earliest to the latest: DQd, DId, DQ, DI. indicates what the outputs represent for the various sampling possibilities.

In the non-extended mode of operation only the "I" input can be sampled in the DES mode. In the extended mode of operation the user can select which input is sampled.

The ADC08D1500 also includes an automatic clock phase background calibration feature which can be used in DES mode to automatically and continuously adjust the clock phase of the I and Q channel. This feature removes the need to adjust the clock phase setting manually and provides optimal Dual-Edge Sampling ENOB performance.

**IMPORTANT NOTE:** The background calibration feature in DES mode does not replace the requirement for On-Command Calibration which should be run before entering DES mode, or if a large swing in ambient temperature is experienced by the device.

**TABLE 1. Input Channel Samples Produced at Data Outputs** 

Data Outputs		Dual-Edge Sampling Mode (DES)			
(Always sourced with respect to fall of DCLK)	Normal Sampling Mode	I-Channel Selected	Q-Channel Selected *		
DI	"I" Input Sampled with Fall of CLK 13 cycles earlier.	"I" Input Sampled with Fall of CLK 13 cycles earlier.	"Q" Input Sampled with Fall of CLK 13 cycles earlier.		
Dld	"I" Input Sampled with Fall of CLK 14 cycles earlier.	"I" Input Sampled with Fall of CLK 14 cycles earlier.	"Q" Input Sampled with Fall of CLK 14 cycles earlier.		
DQ	"Q" Input Sampled with Fall of CLK 13 cycles earlier.	"I" Input Sampled with Rise of CLK 13.5 cycles earlier.	"Q" Input Sampled with Rise of CLK 13.5 cycles earlier.		
DQd	"Q" Input Sampled with Fall of CLK 14 cycles after being sampled.	"I" Input Sampled with Rise of CLK 14.5 cycles earlier.	"Q" Input Sampled with Rise of CLK 14.5 cycles earlier.		

<sup>\*</sup> In DES + normal mode, only the I Channel is sampled. In DES + extended control mode, I or Q channel can be sampled.

#### 1.1.5.2 OutEdge Setting

To help ease data capture in the SDR mode, the output data may be caused to transition on either the positive or the neg-

ative edge of the output data clock (DCLK). This is chosen with the OutEdge input (pin 4). A high on the OutEdge input pin causes the output data to transition on the rising edge of DCLK, while grounding this input causes the output to transi-

tion on the falling edge of DCLK. See 2.4.3 Output Edge Synchronization.

#### 1.1.5.3 Double Data Rate

A choice of single data rate (SDR) or double data rate (DDR) output is offered. With single data rate the output clock (DCLK) frequency is the same as the data rate of the two output buses. With double data rate the DCLK frequency is half the data rate and data is sent to the outputs on both edges of DCLK. DDR clocking is enabled in non-Extended Control mode by allowing pin 4 to float.

#### 1.1.6 The LVDS Outputs

The data outputs, the Out Of Range (OR) and DCLK, are LVDS. Output current sources provide 3 mA of output current to a differential 100 Ohm load when the OutV input (pin 3) is high or 2.2 mA when the OutV input is low. For short LVDS lines and low noise systems, satisfactory performance may be realized with the OutV input low, which results in lower power consumption. If the LVDS lines are long and/or the system in which the ADC08D1500 is used is noisy, it may be necessary to tie the OutV pin high.

The LVDS data output have a typical common mode voltage of 800mV when the  $V_{BG}$  pin is unconnected and floating. This common mode voltage can be increased to 1.2V by tying the  $V_{BG}$  pin to  $V_{A}$  if a higher common mode is required.

**IMPORTANT NOTE:** Tying the  $V_{BG}$  pin to  $V_{A}$  will also increase the differential LVDS output voltage by up to 40 mV.

#### 1.1.7 Power Down

The ADC08D1500 is in the active state when the Power Down pin (PD) is low. When the PD pin is high, the device is in the power down mode. In this power down mode the data output pins (positive and negative) are TRI-STATE and the device power consumption is reduced to a minimal level. The DCLK +/- and OR +/- are not at TRI-STATE. They are weakly pulled

down to ground internally. Therefore when both I and Q are powered down the DCLK +/- and OR +/- should not be terminated to a DC voltage.

A high on the PDQ pin will power down the "Q" channel and leave the "I" channel active. There is no provision to power down the "I" channel independently of the "Q" channel. Upon return to normal operation, the pipeline will contain meaningless information.

If the PD input is brought high while a calibration is running, the device will not go into power down until the calibration sequence is complete. However, if power is applied and PD is already high, the device will not begin the calibration sequence until the PD input goes low. If a manual calibration is requested while the device is powered down, the calibration will not begin at all. That is, the manual calibration input is completely ignored in the power down state. Calibration will function with the "Q" channel powered down, but that channel will not be calibrated if PDQ is high. If the "Q" channel is subsequently to be used, it is necessary to perform a calibration after PDQ is brought low.

#### 1.2 NORMAL/EXTENDED CONTROL

The ADC08D1500 may be operated in one of two modes. In the simpler standard control mode, the user affects available configuration and control of the device through several control pins. The "extended control mode" provides additional configuration and control options through a serial interface and a set of 9 registers. The two control modes are selected with pin 14 (FSR/ECE: Extended Control Enable). The choice of control modes is required to be a fixed selection and is not intended to be switched dynamically while the device is operational.

*Table 2* shows how several of the device features are affected by the control mode chosen.

**TABLE 2. Features and Modes** 

Feature	Normal Control Mode	Extended Control Mode		
SDR or DDR Clocking	DDR Clocking selected with pin 4 floating. SDR clocking selected when pin 4 not floating.	Selected with nDE in the Configuration Register (1h; bit-10). When the device is in DDR mode, address 1h, bit-8 must be set to 0b.		
DDR Clock Phase	Not Selectable (0° Phase Only)	Selected with DCP in the Configuration Register (1h; bit-11).		
SDR Data transitions with rising or falling DCLK edge	SDR Data transitions with rising edge of DCLK+ when pin 4 is high and on falling edge when low.	Selected with OE in the Configuration Register (1h; bit-8).		
LVDS output level	Normal differential data and DCLK amplitude selected when pin 3 is high and reduced amplitude selected when low.	Selected with the OV in the Configuration Register (1h; bit-9).		
Power-On Calibration Delay	Short delay selected when pin 127 is low and longer delay selected when high.	Short delay only.		
Full-Scale Range	Normal input full-scale range selected when pin 14 is high and reduced range when low. Selected range applies to both channels.	Up to 512 step adjustments over a nominal range specified in <i>1.4</i> REGISTER DESCRIPTION. Selected using the Input Full-Scale Adjust register (3h; bits-7 thru 15).		
Input Offset Adjust	Not possible	512 steps of adjustment using the Input Offset register (2h; bits-7 thru 15) as specified in		
Dual Edge Sampling Selection	Enabled with pin 127	Enabled through DES Enable Register.		
Dual Edge Sampling Input Channel Selection	Only I-Channel Input can be used	Either I- or Q-Channel input may be sampled by both ADCs.		
DES Sampling Clock Adjustment	The Clock Phase is adjusted automatically	Automatic Clock Phase control can be selected by setting bit 14 in the DES Enable Register (Dh). The clock phase can also be adjusted manually through the Coarse & Fine Registers (Eh and Fh).		

The default state of the Extended Control Mode is set upon power-on reset (internally performed by the device) and is shown in *Table 3*.

TABLE 3. Extended Control Mode Operation (Pin 14 Floating)

( 9)							
Feature	Extended Control Mode Default State						
SDR or DDR Clocking	DDR Clocking						
DDR Clock Phase	Data changes with DCLK edge (0° phase)						
LVDS Output Amplitude	Normal amplitude (710 mV <sub>P-P</sub> )						
Calibration Delay	Short Delay						
Full-Scale Range	700 mV nominal for both channels						
Input Offset Adjust	No adjustment for either channel						
Dual Edge Sampling (DES)	Not enabled						

#### 1.3 THE SERIAL INTERFACE

The 3-pin serial interface is enabled only when the device is in the Extended Control mode. The pins of this interface are Serial Clock (SCLK), Serial Data (SDATA) and Serial Interface Chip Select ( $\overline{SCS}$ ) Eight write only registers are accessible through this serial interface.

**SCS:** This signal should be asserted low while accessing a register through the serial interface. Setup and hold times with respect to the SCLK must be observed.

**SCLK:** Serial data input is accepted with the rising edge of this signal. There is no minimum frequency requirement for SCLK.

**SDATA:** Each register access requires a specific 32-bit pattern at this input. This pattern consists of a header, register address and register value. The data is shifted in MSB first. Setup and hold times with respect to the SCLK must be observed. See the Timing Diagram.

Each Register access consists of 32 bits, as shown in *Figure* 5 of the Timing Diagrams. The fixed header pattern is 0000 0000 0001 (eleven zeros followed by a 1). The loading sequence is such that a "0" is loaded first. These 12 bits form the header. The next 4 bits are the address of the register that is to be written to and the last 16 bits are the data written to

the addressed register. The addresses of the various registers are indicated in *Table 4*.

Refer to the Register Description (Section 1.4) for information on the data to be written to the registers.

Subsequent register accesses may be performed immediately, starting with the 33rd SCLK. This means that the  $\overline{SCS}$  input does not have to be de-asserted and asserted again between register addresses. It is possible, although not recommended, to keep the  $\overline{SCS}$  input permanently enabled (at a logic low) when using extended control.

**IMPORTANT NOTE:** The Serial Interface should not be used when calibrating the ADC. Doing so will impair the performance of the device until it is re-calibrated correctly. Programming the serial registers will also reduce dynamic performance of the ADC for the duration of the register access time

**TABLE 4. Register Addresses** 

	4-Bit Address												
	Loading Sequence: A3 loaded after H0, A0 loaded last												
	A3	loaded	after H0	, A0 loa	aded last								
A3	A2	A1	A0	Hex	Register Addressed								
0	0	0	0	0h	Reserved								
0	0	0	1	1h	Configuration								
0	0	1	0	2h	"I" Ch Offset								
0	0	1	1	3h	"I" Ch Full-Scale								
		'	'	011	Voltage Adjust								
0	1	0	0	4h	Reserved								
0	1	0	1	5h	Reserved								
0	1	1	0	6h	Reserved								
0	1	1	1	7h	Reserved								
1	0	0	0	8h	Reserved								
1	0	0	1	9h	Reserved								
1	0	1	0	Ah	"Q" Ch Offset								
1	0	1	1	Bh	"Q" Ch Full-Scale								
1	U	ı	ı	DII	Voltage Adjust								
1	1	0	0	Ch	Reserved								
1	1	0	1	Dh	DES Enable								
1	1	1	0	Eh	DES Coarse Adjust								
1	1	1	1	Fh	DES Fine Adjust								

#### 1.4 REGISTER DESCRIPTION

Eight write-only registers provide several control and configuration options in the Extended Control Mode. These registers have no effect when the device is in the Normal Control Mode. Each register description below also shows the Power-On Reset (POR) state of each control bit.

## **Configuration Register**

Addr: 1h (0001b)	W only	(0xB2FF)
------------------	--------	----------

D15	D14	D13	D12	D11	D10	D9	D8
1	0	1	DCS	DCP	nDE	OV	OE
D7	D6	D5	D4	D3	D2	D1	D0
1	1	1	1	1	1	1	1

Bit 15 Must be set to 1b

Bit 14 Must be set to 0b

Bit 13 Must be set to 1b

Bit 12 DCS: Duty Cycle Stabilizer. When this bit is set to 1b , a duty cycle stabilization circuit is applied to the clock input. When this bit is set to 0b the stabilization circuit is disabled.

POR State: 1b

Bit 11 DCP: DDR Clock Phase. This bit only has an effect in the DDR mode. When this bit is set to 0b, the DCLK edges are time-aligned with the data bus edges ("0° Phase"). When this bit is set to 1b, the DCLK edges are placed in the middle of the data bit-cells ("90° Phase"), using the one-half speed DCLK shown in Figure 4 as the phase reference.

POR State: 0b

Bit 10 nDE: DDR Enable. When this bit is set to 0b, data bus clocking follows the DDR (Double Data Rate) mode whereby a data word is output with each rising and falling edge of DCLK. When this bit is set to a 1b, data bus clocking follows the SDR (single data rate) mode whereby each data word is output with either the rising or falling edge of DCLK, as determined by the OutEdge bit.

POR State: 0b

Bit 9 OV: Output Voltage. This bit determines the LVDS outputs' voltage amplitude and has the same function as the OutV pin that is used in the normal control mode. When this bit is set to 1b, the standard output amplitude of 710 mV<sub>P-P</sub> is used. When this bit is set to 0b, the reduced output amplitude of 510 mV<sub>P-P</sub> is used.

POR State: 1b

Bit 8 OE: Output Edge. This bit selects the DCLK edge with which the data words transition in the SDR mode and has the same effect as the OutEdge pin in the normal control mode. When this bit is 1, the data outputs change with the rising edge of DCLK+. When this bit is 0, the data output change with the falling edge of DCLK+.

POR State: 0b

Bits 7:0 Must be set to 1b.

#### I-Channel Offset

Addr: 2h (0010b) W only (0x007F)

D15	D14	D13	D12	D11	D10	D9	D8			
(MSB)	(MSB) Offset Value									
D7	D6	D5	D4	D3	D2	D1	D0			
Sign	1	1	1	1	1	1	1			

Bits 15:8 Offset Value. The input offset of the I-Channel ADC is adjusted linearly and monotonically by the value in this field. 00h provides a nominal zero offset, while FFh provides a nominal 45 mV of offset. Thus, each code step provides 0.176 mV of offset.

POR State: 0000 0000 b

Bit 7 Sign bit. 0b gives positive offset, 1b gives

negative offset. POR State: 0b

Bit 6:0 Must be set to 1b

#### I-Channel Full-Scale Voltage Adjust

Addr: 3h (0011b) W only (0x807F)

D15	D14	D13	D12	D11	D10	D9	D8	
(MSB)	(MSB) Adjust Value							
D7	D6	D5	D4	D3	D2	D1	D0	
(LSB)	1	1	1	1	1	1	1	

Bit 15:7 Full Scale Voltage Adjust Value. The input full-scale voltage or gain of the I-Channel ADC is adjusted linearly and monotonically with a 9 bit data value. The adjustment range is  $\pm 20\%$  of the nominal 700 mV<sub>P-P</sub> differential value.

0000 0000 0 560mV<sub>P-P</sub> 1000 0000 0 700mV<sub>P-P</sub>

**Default Value** 

1111 1111 1 840mV<sub>P-P</sub>

For best performance, it is recommended that the value in this field be limited to the range of 0110 0000 0b to 1110 0000 0b. i.e., limit the amount of adjustment to  $\pm 15\%$ . The remaining  $\pm 5\%$  headroom allows for the ADC's own full scale variation. A gain adjustment does not require ADC re-calibration.

POR State: 1000 0000 0b (no adjustment)

Bits 6:0 Must be set to 1b

#### Q-Channel Offset

Addr: Ah (1010b) W only (0x007F)

D15	D14	D13	D12	D11	D10	D9	D8	
(MSB) Offset Value								
D7	D6	D5	D4	D3	D2	D1	D0	
Sign	1	1	1	1	1	1	1	

Bit 15:8 Offset Value. The input offset of the Q-Channel ADC is adjusted linearly and monotonically by the value in this field. 00h provides a nominal zero offset, while FFh provides a nominal 45 mV of offset. Thus, each code step provides about 0.176 mV of

POR State: 0000 0000 b

Bit 7 Sign bit. 0b gives positive offset, 1b gives

negative offset. POR State: 0b

Bit 6:0 Must be set to 1b

offset.

#### Q-Channel Full-Scale Voltage Adjust

Addr: Bh (1011b) W only (0x807F)

D15	D14	D13	D12	D11	D10	D9	D8	
(MSB) Adjust Value								
D7	D6	D5	D4	D3	D2	D1	D0	
(LSB)	1	1	1	1	1	1	1	

Bit 15:7 Full Scale Voltage Adjust Value. The input full-scale voltage or gain of the I-Channel ADC is adjusted linearly and monotonically with a 9 bit data value. The adjustment range is  $\pm 20\%$  of the nominal 700 mV<sub>P-P</sub> differential value.

For best performance, it is recommended that the value in this field be limited to the range of 0110 0000 0b to 1110 0000 0b. i.e., limit the amount of adjustment to  $\pm 15\%$ . The remaining  $\pm 5\%$  headroom allows for the ADC's own full scale variation. A gain adjustment does not require ADC re-calibration.

POR State: 1000 0000 0b (no adjustment)

Bits 6:0 Must be set to 1b

#### **DES Enable**

Addr: Dh (1101b) W only (0x3FFF)

D15	D14	D13	D12	D11	D10	D9	D8
DEN	ACP	1	1	1	1	1	1
D7	D6	D5	D4	D3	D2	D1	D0
1	1	1	1	1	1	1	1

Bit 15 DES Enable. Setting this bit to 1b enables the Dual Edge Sampling mode. In this mode the ADCs in this device are used to sample and convert the same analog input in a time-interleaved manner, accomplishing a sample rate of twice the input clock rate. When this bit is set to 0b, the device operates in the normal dual channel mode.

POR State: 0b

Bit 14 Automatic Clock Phase (ACP) Control. Setting this bit to 1b enables the Automatic Clock Phase Control. In this mode the DES Coarse and Fine manual controls are disabled. A phase detection circuit continually adjusts the I and Q sampling edges to be 180 degrees out of phase. When this bit is set to 0b, the sample (input) clock delay between the I and Q channels is set manually using the DES Coarse and Fine Adjust registers. (See Section 2.4.5 for important application information) Using the ACP Control option is recommended over the manual DES settings.

POR State: 0b
Bits 13:0 Must be set to 1b

#### **DES Coarse Adjust**

W only (0x07FF)

Addr: Eh (1110b)

D15	D14	D13	D12	D11	D10	D9	D8
IS	ADS		CAM		1	1	1
D7	D6	D5	D4	D3	D2	D1	D0

Bit 15 Input Select. When this bit is set to 0b the "I" input is operated upon by both ADCs. When this bit is set to 1b the "Q" input is operated on by both ADCs.

POR State: 0b

Bit 14 Adjust Direction Select. When this bit is set to 0b, the programmed delays are applied to the "I" channel sample clock while the "Q" channel sample clock remains fixed. When this bit is set to 1b, the programmed delays are applied to the "Q" channel sample clock while the "I" channel sample clock remains fixed.

POR State: 0b

Bits 13:11 Coarse Adjust Magnitude. Each code value in this field delays either the "I" channel or the "Q" channel sample clock (as determined by the ADS bit) by approximately 20 picoseconds. A value of 000b in this field causes zero adjustment.

POR State: 000b Bits 10:0 Must be set to 1b

#### **DES Fine Adjust**

Addr: Fh (1111b) W only (0x007F)

D15	D14	D13	D12	D11	D10	D9	D8
(MSB)	FAM						
D7	D6	D5	D4	D3	D2	D1	D0
(LSB)	1	1	1	1	1	1	1

Bits 15:7 Fine Adjust Magnitude. Each code value in this field delays either the "I" channel or the "Q" channel sample clock (as determined by the ADS bit of the DES Coarse Adjust Register) by approximately 0.1 ps. A value of 0000 0000 0b in this field causes zero adjustment. Note that the amount of adjustment achieved with each code will vary with the device conditions as well as with the Coarse Adjustment value chosen.

POR State: 0000 0000 0b

Bit 6:0 Must be set to 1b

#### 1.4.1 Note Regarding Extended Mode Offset Correction

When using the I or Q channel Offset Adjust registers, the following information should be noted.

For offset values of +0000 0000 and -0000 0000, the actual offset is not the same. By changing only the sign bit in this case, an offset step in the digital output code of about 1/10th of an LSB is experienced. This is shown more clearly in the Figure below.




FIGURE 10. Extended Mode Offset Behavior

#### 1.5 MULTIPLE ADC SYNCHRONIZATION

The ADC08D1500 has the capability to precisely reset its sampling clock input to DCLK output relationship as deter-

mined by the user-supplied DCLK\_RST pulse. This allows multiple ADCs in a system to have their DCLK (and data) outputs transition at the same time with respect to the shared CLK input that all the ADCs use for sampling.

The DCLK\_RST signal must observe some timing requirements that are shown in Figure 6, Figure 7 and Figure 8 of the Timing Diagrams. The DCLK\_RST pulse must be of a minimum width and its deassertion edge must observe setup and hold times with respect to the CLK input rising edge. These timing specifications are listed as  $t_{\rm RH},\ t_{\rm RS},\$ and  $t_{\rm RPW}$  in the Converter Electrical Characteristics.

The DCLK\_RST signal can be asserted asynchronous to the input clock. If DCLK RST is asserted, the DCLK output is held in a designated state. The state in which DCLK is held during the reset period is determined by the mode of operation (SDR/ DDR) and the setting of the Output Edge configuration pin or bit. (Refer to Figure 6, Figure 7 and Figure 8 for the DCLK reset state conditions). Therefore, depending upon when the DCLK\_RST signal is asserted, there may be a narrow pulse on the DCLK line during this reset event. When the DCLK RST signal is de-asserted in synchronization with the CLK rising edge, the next CLK falling edge synchronizes the DCLK output with those of other ADC08D1500s in the system. The DCLK output is enabled again after a constant delay (relative to the input clock frequency) which is equal to the CLK input to DCLK output delay (t<sub>SD</sub>). The device always exhibits this delay characteristic in normal operation.

The DCLK\_RST pin should NOT be brought high while the calibration process is running (while CalRun is high). Doing so could cause a digital glitch in the digital circuitry, resulting in corruption and invalidation of the calibration.

# 2.0 Applications Information

#### 2.1 THE REFERENCE VOLTAGE

The voltage reference for the ADC08D1500 is derived from a 1.254V bandgap reference, a buffered version of which is made available at pin 31,  $V_{BG},$  for user convenience. This output has an output current capability of  $\pm 100~\mu A$  and should be buffered if more current than this is required.

The internal bandgap-derived reference voltage has a nominal value of  $V_{\rm IN}$ , as determined by the FSR pin and described in 1.1.4 The Analog Inputs.

There is no provision for the use of an external reference voltage, but the full-scale input voltage can be adjusted through a Configuration Register in the Extended Control mode, as explained in 1.2 NORMAL/EXTENDED CONTROL.

Differential input signals up to the chosen full-scale level will be digitized to 8 bits. Signal excursions beyond the full-scale range will be clipped at the output. These large signal excursions will also activate the OR output for the time that the signal is out of range. See 2.2.2 Out Of Range (OR) Indication.

One extra feature of the  $V_{BG}$  pin is that it can be used to raise the common mode voltage level of the LVDS outputs. The output offset voltage ( $V_{OS}$ ) is typically 800mV when the  $V_{BG}$  pin is used as an output or left unconnected. To raise the LVDS offset voltage to a typical value of 1200mV the  $V_{BG}$  pin can be connected directly to the supply rails.

#### 2.2 THE ANALOG INPUT

The analog input is a differential one to which the signal source may be a.c. coupled or d.c. coupled. In the normal mode, the full-scale input range is selected using the FSR pin as specified in the Converter Electrical Characteristics. In the

Extended Control mode, the full-scale input range is selected by programming the Full-Scale Voltage Adjust register through the Serial Interface. For best performance when adjusting the input full-scale range in the Extended Control, refer to 1.4 REGISTER DESCRIPTION. for guidelines on limiting the amount of adjustment.

Table 5 gives the input to output relationship with the FSR pin high when the normal (non-extended) mode is used. With the FSR pin grounded, the millivolt values; in are reduced to 75% of the values indicated. In the Extended Control Mode, these values will be determined by the full scale range and offset settings in the Control Registers.

TABLE 5. DIFFERENTIAL INPUT TO OUTPUT
RELATIONSHIP
(Non-Extended Control Mode, FSR High)

V <sub>IN</sub> +	V <sub>IN</sub> -	Output Code	
V <sub>CM</sub> – 217.5mV	V <sub>CM</sub> + 217.5mV	0000 0000	
V <sub>CM</sub> – 109 mV	V <sub>CM</sub> + 109 mV	0100 0000	
V	V	0111 1111 /	
V <sub>CM</sub>	V <sub>CM</sub>	1000 0000	
V <sub>CM</sub> + 109 mV	V <sub>CM</sub> –109 mV	1100 0000	
V <sub>CM</sub> + 217.5mV	V <sub>CM</sub> – 217.5mV	1111 1111	

The buffered analog inputs simplify the task of driving these inputs and the RC pole that is generally used at sampling ADC inputs is not required. If it is desired to use an amplifier circuit before the ADC, use care in choosing an amplifier with adequate noise and distortion performance and adequate gain at the frequencies used for the application.

Note that a precise d.c. common mode voltage must be present at the ADC inputs. This common mode voltage,  $V_{\text{CMO}}$ , is provided on-chip when a.c. input coupling is used and the input signal is a.c. coupled to the ADC.

When the inputs are a.c. coupled, the  $V_{CMO}$  output *must* be grounded, as shown in *Figure 11*. This causes the on-chip  $V_{CMO}$  voltage to be connected to the inputs through on-chip 50k-Ohm resistors.

**IMPORTANT NOTE:** An Analog input channel that is not used (e.g. in DES Mode) should be left floating when the inputs are a.c. coupled. Do not connect an unused analog input to ground.




FIGURE 11. Differential Input Drive

When the d.c. coupled mode is used, a common mode voltage must be provided at the differential inputs. This common mode voltage should track the  $V_{CMO}$  output pin. Note that the  $V_{CMO}$  output potential will change with temperature. The common mode output of the driving device should track this change.

**IMPORTANT NOTE:** An analog input channel that is not used (e.g. in DES Mode) should be tied to the  $V_{CMO}$  voltage when the inputs are d.c. coupled. Do not connect unused analog inputs to ground.

Full-scale distortion performance falls off rapidly as the input common mode voltage deviates from  $V_{CMO}$ . This is a direct result of using a very low supply voltage to minimize power. Keep the input common voltage within 50 mV of  $V_{CMO}$ .

Performance of the ADC08D1500 is as good in the d.c. coupled mode as it is in the a.c. coupled mode, provided the input common mode voltage at both analog inputs remain within 50 mV of  $V_{\rm CMO}$ .

#### 2.2.1 Handling Single-Ended Input Signals

There is no provision for the ADC08D1500 to adequately process single-ended input signals. The best way to handle single-ended signals is to convert them to differential signals before presenting them to the ADC. The easiest way to accomplish single-ended to differential signal conversion is with an appropriate balun-connected transformer, as shown in *Figure 12*.

#### 2.2.1.1 A.C. Coupled Input

The easiest way to accomplish single-ended a.c. input to differential a.c. signal is with an appropriate balun-connected transformer, as shown in *Figure 12*.




FIGURE 12. Single-Ended to Differential Signal Conversion Using a Balun

Figure 12 is a generic depiction of a single-ended to differential signal conversion using a balun. The circuitry specific to the balun will depend on the type of balun selected and the overall board layout. It is recommended that the system designer contact the manufacturer of the balun they have selected to aid in designing the best performing single-ended to differential conversion circuit using that particular balun.

When selecting a balun, it is important to understand the input architecture of the ADC. There are specific balun parameters of which the system designer should be mindful. They should match the impedance of their analog source to the ADC08D1500's on-chip 100 differential input termination resistor. The range of this termination resistor is described in the electrical table as the specification  $\rm R_{IN}$ .

Also, as a result of the ADC architecture, the phase and amplitude balance are important. The lowest possible phase and amplitude imbalance is desired when selecting a balun. The phase imbalance should be no more than ±2.5° and the amplitude imbalance should be limited to less than 1dB at the desired input frequency range. Finally, when selecting a balun, the VSWR (Voltage Standing Wave Ratio), bandwidth and insertion loss of the balun should also be considered. The VSWR aids in determining the overall transmission line termination capability of the balun when interfacing to the ADC input. The insertion loss should be considered so that the sig-

nal at the balun output is within the specified input range of the ADC as described in the Converter Electrical Characteristics as the specification  $V_{\rm IN}$ .

#### 2.2.1.2 D.C. Coupled Input

When d.c. coupling to the ADC08D1500 analog inputs is required, single-ended to differential conversion may be easily accomplished with the LMH6555, as shown in Figure 13. In such applications, the LMH6555 performs the task of single-ended to differential conversion while delivering low distortion and noise, as well as output balance, that supports the operation of the ADC08D1500. Connecting the ADC08D1500  $\rm V_{CMO}$  pin to the  $\rm V_{CMC}$  REF pin of the LMH6555, through the appropriate buffer, will ensure that the ADC08D1500 common mode input voltage is as needed for optimum performance of the ADC08D1500. See Figure 13. The LMV321 was chosen as the buffer in Figure 13 for its low voltage operation and reasonable offset voltage.

Be sure to limit output current from the ADC08D1500  $V_{CMO}$  pin to 100  $\mu A$ .




FIGURE 13. Example of Servoing the Analog Input with  $V_{CMO}$ 

Figure 13, R  $_{ADJ_{-}}$  and R  $_{ADJ_{+}}$  are used to adjust the differential offset that can be measured at the ADC inputs V $_{IN_{+}}$  / V $_{IN_{-}}$ . An unadjusted positive offset with reference to V $_{IN_{-}}$  greater than I15mVI should be reduced with a resistor in the R $_{ADJ_{-}}$  position. Likewise, an unadjusted negative offset with reference to V $_{IN_{-}}$  greater than I15mVI should be reduced with a resistor in the R $_{ADJ_{+}}$  position. gives suggested R $_{ADJ_{-}}$  and R $_{ADJ_{+}}$  values for various unadjusted differential offsets to bring the V $_{IN_{+}}$  / V $_{IN_{-}}$  offset back to within I15mVI.

**TABLE 6. D.C. Coupled Offset Adjustment** 

Unadjusted Offset Reading	Resistor Value
0mV to 10mV	no resistor needed
11mV to 30mV	20.0kΩ
31mV to 50mV	10.0kΩ
51mV to 70mV	6.81kΩ
71mV to 90mV	4.75kΩ
91mV to 110mV	3.92kΩ

#### 2.2.2 Out Of Range (OR) Indication

When the conversion result is clipped the Out of Range output is activated such that OR+ goes high and OR- goes low. This output is active as long as accurate data on either or both of the buses would be outside the range of 00h to FFh.

#### 2.2.3 Full-Scale Input Range

As with all A/D Converters, the input range is determined by the value of the ADC's reference voltage. The reference voltage of the ADC08D1500 is derived from an internal band-gap reference. The FSR pin controls the effective reference voltage of the ADC08D1500 such that the differential full-scale input range at the analog inputs is a normal amplitude with the FSR pin high, or a reduced amplitude with FSR pin low as defined by the specification  $\rm V_{IN}$  in the Converter Electrical Characteristics. Best SNR is obtained with FSR high, but better distortion and SFDR are obtained with the FSR pin low.

#### 2.3 THE CLOCK INPUTS

The ADC08D1500 has differential LVDS clock inputs, CLK+ and CLK-, which must be driven with an a.c. coupled, differential clock signal. Although the ADC08D1500 is tested and its performance is guaranteed with a differential 1.5 GHz clock, it typically will function well with input clock frequencies indicated in the Converter Electrical Characteristic. The clock inputs are internally terminated and biased. The input clock signal must be capacitively coupled to the clock pins as indicated in *Figure 14*.

Operation up to the sample rates indicated in the Converter Electrical Characteristic is typically possible if the maximum ambient temperatures indicated are not exceeded. Operating at higher sample rates than indicated for the given ambient temperature may result in reduced device reliability and product lifetime. This is because of the higher power consumption and die temperatures at high sample rates. Important also for reliability is proper thermal management. See 2.6.2 Thermal Management.




FIGURE 14. Differential (LVDS) Input Clock Connection

The differential input clock line pair should have a characteristic impedance of  $100\Omega$  and (when using a balun), be terminated at the clock source in that  $(100\Omega)$  characteristic impedance. The input clock line should be as short and as direct as possible. The ADC08D1500 clock input is internally terminated with an untrimmed  $100\Omega$  resistor.

Insufficient input clock levels will result in poor dynamic performance. Excessively high input clock levels could cause a change in the analog input offset voltage. To avoid these problems, keep the clock level within the range specified as  $V_{\text{ID}}$  in the Converter Electrical Characteristics.

The low and high times of the input clock signal can affect the performance of any A/D Converter. The ADC08D1500 features a duty cycle clock correction circuit which can maintain performance over temperature. The ADC will meet its performance specification if the input clock high and low times are maintained within the duty cycle range as specified in the Converter Electrical Characteristics.

High speed, high performance ADCs such as the AD-C08D1500 require a very stable input clock signal with mini-

mum phase noise or jitter. ADC jitter requirements are defined by the ADC resolution (number of bits), maximum ADC input frequency and the input signal amplitude relative to the ADC input full scale range. The maximum jitter (the sum of the jitter from all sources) allowed to prevent a jitter-induced reduction in SNR is found to be

$$t_{J(MAX)} = (V_{INFSR} / V_{IN(P-P)}) \times (1/(2^{(N+1)} \times \pi \times f_{IN}))$$

where  $t_{J(MAX)}$  is the rms total of all jitter sources in seconds,  $V_{IN(P-P)}$  is the peak-to-peak analog input signal,  $V_{INFSR}$  is the full-scale range of the ADC, "N" is the ADC resolution in bits and  $f_{IN}$  is the maximum input frequency, in Hertz, to the ADC analog input.

Note that the maximum jitter described above is the RSS sum of the jitter from all sources, including that in the ADC input clock, that added by the system to the ADC input clock and input signals and that added by the ADC itself. Since the effective jitter added by the ADC is beyond user control, the best the user can do is to keep the sum of the externally added input clock jitter and the jitter added by the analog circuitry to the analog signal to a minimum.

Input clock amplitudes above those specified in the Converter Electrical Characteristics may result in increased input offset voltage. This would cause the converter to produce an output code other than the expected 127/128 when both input pins are at the same potential.

#### 2.4 CONTROL PINS

Six control pins (without the use of the serial interface) provide a wide range of possibilities in the operation of the ADC08D1500 and facilitate its use. These control pins provide Full-Scale Input Range setting, Self Calibration, Calibration Delay, Output Edge Synchronization choice, LVDS Output Level choice and a Power Down feature.

#### 2.4.1 Full-Scale Input Range Setting

Power-on calibration begins after a time delay following the application of power. This time delay is determined by the setting of CalDly, as described in the Calibration Delay Section, below.

The calibration process will be not be performed if the CAL pin is high at power up. In this case, the calibration cycle will not begin until the on-command calibration conditions are met. The ADC08D1500 will function with the CAL pin held high at power up, but no calibration will be done and performance will be impaired. A manual calibration, however, may be performed after powering up with the CAL pin high. See .

#### 2.4.2 Self Calibration

The ADC08D1500 self-calibration must be run to achieve specified performance. The calibration procedure is run upon power-up and can be run any time on command. The calibration procedure is exactly the same whether there is an input clock present upon power up or if the clock begins some time after application of power. The CalRun output indicator is high while a calibration is in progress. Note that the DCLK outputs are not active during a calibration cycle, therefore it is not recommended as a system clock.

#### 2.4.2.1 Power-On Calibration

Power-on calibration begins after a time delay following the application of power. This time delay is determined by the setting of CalDly, as described in the Calibration Delay Section, below.

The calibration process will be not be performed if the CAL pin is high at power up. In this case, the calibration cycle will not begin until the on-command calibration conditions are

met. The ADC08D1500 will function with the CAL pin held high at power up, but no calibration will be done and performance will be impaired. A manual calibration, however, may be performed after powering up with the CAL pin high. See On-Command Calibration Section 2.4.2.2.

The internal power-on calibration circuitry comes up in an unknown logic state. If the input clock is not running at power up and the power on calibration circuitry is active, it will hold the analog circuitry in power down and the power consumption will typically be less than 200 mW. The power consumption will be normal after the clock starts.

#### 2.4.2.2 On-Command Calibration

To initiate an on-command calibration, bring the CAL pin high for a minimum of  $t_{\text{CAL\_H}}$  input clock cycles after it has been low for a minimum of  $t_{\text{CAL\_L}}$  input clock cycles. Holding the CAL pin high upon power up will prevent execution of power-on calibration until the CAL pin is low for a minimum of  $t_{\text{CAL\_L}}$  input clock cycles, then brought high for a minimum of another  $t_{\text{CAL\_H}}$  input clock cycles. The calibration cycle will begin  $t_{\text{CAL\_H}}$  input clock cycles after the CAL pin is thus brought high. The CalRun signal should be monitored to determine when the calibration cycle has completed.

The minimum  $t_{CAL\_H}$  and  $t_{CAL\_L}$  input clock cycle sequences are required to ensure that random noise does not cause a calibration to begin when it is not desired. As mentioned in 1.1.1 Self-Calibration for best performance, a self calibration should be performed 20 seconds or more after power up and repeated when the operating temperature changes significantly according to the particular system performance requirements. ENOB drops slightly as junction temperature increases and executing a new self calibration cycle will essentially eliminate the change.

During a Power-On calibration cycle, both the ADC and the input termination resistor are calibrated. As ENOB changes slightly with junction temperature, an On-Command calibration can be executed to bring the performance of the ADC in line.

#### 2.4.2.3 Calibration Delay

The CalDly input (pin 127) is used to select one of two delay times after the application of power to the start of calibration, as described in 1.1.1 Self-Calibration. The calibration delay values allow the power supply to come up and stabilize before calibration takes place. With no delay or insufficient delay, calibration would begin before the power supply is stabilized at its operating value and result in non-optimal calibration coefficients. If the PD pin is high upon power-up, the calibration delay counter will be disabled until the PD pin is brought low. Therefore, holding the PD pin high during power up will further delay the start of the power-up calibration cycle. The best setting of the CalDly pin depends upon the power-on settling time of the power supply.

Note that the calibration delay selection is not possible in the Extended Control mode and the short delay time is used.

#### 2.4.3 Output Edge Synchronization

DCLK signals are available to help latch the converter output data into external circuitry. The output data can be synchronized with either edge of these DCLK signals. That is, the output data transition can be set to occur with either the rising edge or the falling edge of the DCLK signal, so that either edge of that DCLK signal can be used to latch the output data into the receiving circuit.

When OutEdge (pin 4) is high, the output data is synchronized with (changes with) the rising edge of the DCLK+ (pin 82).

When OutEdge is low, the output data is synchronized with the falling edge of DCLK+.

At the very high speeds of which the ADC08D1500 is capable, slight differences in the lengths of the DCLK and data lines can mean the difference between successful and erroneous data capture. The OutEdge pin is used to capture data on the DCLK edge that best suits the application circuit and layout.

#### 2.4.4 LVDS Output Level Control

The output level can be set to one of two levels with OutV (pin3). The strength of the output drivers is greater with OutV high. With OutV low there is less power consumption in the output drivers, but the lower output level means decreased noise immunity.

For short LVDS lines and low noise systems, satisfactory performance may be realized with the OutV input low. If the LVDS lines are long and/or the system in which the ADC08D1500 is used is noisy, it may be necessary to tie the OutV pin high.

#### 2.4.5 Dual Edge Sampling

The Dual Edge Sampling (DES) feature causes one of the two input pairs to be routed to both ADCs. The other input pair is deactivated. One of the ADCs samples the input signal on one input clock edge (duty cycle corrected), the other samples the input signal on the other input clock edge (duty cycle corrected). The result is a 1:4 demultiplexed output with a sample rate that is twice the input clock frequency.

To use this feature in the non-enhanced control mode, allow pin 127 to float and the signal at the "I" channel input will be sampled by both converters. The Calibration Delay will then only be a short delay.

In the enhanced control mode, either input may be used for dual edge sampling. See Section 1.1.5.1.

#### **IMPORTANT NOTES:**

- 1) For the Extended Control Mode When using the Automatic Clock Phase Control feature in dual edge sampling mode, it is important that the automatic phase control is disabled (set bit 14 of DES Enable register Dh to 0) before the ADC is powered up. Not doing so may cause the device not to wake-up from the power down state.
- 2) For the Non-Extended Control Mode When the ADC08D1500 is powered up and DES mode is required, ensure that pin 127 (CalDly/DES/ $\overline{SCS}$ ) is initially pulled low during or after the power up sequence. The pin can then be allowed to float or be tied to  $V_A/2$  to enter the DES mode. This will ensure that the part enters the DES mode correctly.
- 3) The automatic phase control should also be disabled if the input clock is interrupted or stopped for any reason. This is also the case if a large abrupt change in the clock frequency occurs.
- 4) If a calibration of the ADC is required in Auto DES mode, the device must be returned to the Normal Mode of operation before performing a calibration cycle. Once the Calibration has been completed, the device can be returned to the Auto DES mode and operation can resume.

#### 2.4.6 Power Down Feature

The Power Down pins (PD and PDQ) allow the ADC08D1500 to be entirely powered down (PD) or the "Q" channel to be powered down and the "I" channel to remain active. See Section 1.1.7 for details on the power down feature.

The digital data (+/-) output pins are put into a high impedance state when the PD pin for the respective channel is high. Upon return to normal operation, the pipeline will contain meaningless information and must be flushed.

If the PD input is brought high while a calibration is running, the device will not go into power down until the calibration sequence is complete. However, if power is applied and PD is already high, the device will not begin the calibration sequence until the PD input goes low. If a manual calibration is requested while the device is powered down, the calibration will not begin at all. That is, the manual calibration input is completely ignored in the power down state.

#### 2.5 THE DIGITAL OUTPUTS

The ADC08D1500 demultiplexes the output data of each of the two ADCs on the die onto two LVDS output buses (total of four buses, two for each ADC). For each of the two converters, the results of successive conversions started on the odd falling edges of the CLK+ pin are available on one of the two LVDS buses, while the results of conversions started on the even falling edges of the CLK+ pin are available on the other LVDS bus. This means that, the word rate at each LVDS bus is 1/2 the ADC08D1500 input clock rate and the two buses must be multiplexed to obtain the entire 1.5 GSPS conversion result.

Since the minimum recommended input clock rate for this device is 200 MSPS (normal non DES mode), the effective rate can be reduced to as low as 100 MSPS by using the results available on just one of the the two LVDS buses and a 200 MHz input clock, decimating the 200 MSPS data by two. There is one LVDS output clock pair (DCLK+/-) available for use to latch the LVDS outputs on all buses. Whether the data

is sent at the rising or falling edge of DCLK is determined by the sense of the OutEdge pin, as described in Section 2.4.3. DDR (Double Data Rate) clocking can also be used. In this mode a word of data is presented with each edge of DCLK, reducing the DCLK frequency to 1/4 the input clock frequency. See the Timing Diagram section for details.

The OutV pin is used to set the LVDS differential output levels. See Section 2.4.4.

The output format is Offset Binary. Accordingly, a full-scale input level with  $V_{IN}^+$  positive with respect to  $V_{IN}^-$  will produce an output code of all ones, a full-scale input level with  $V_{IN}^-$  positive with respect to  $V_{IN}^+$  will produce an output code of all zeros and when  $V_{IN}^+$  and  $V_{IN}^-$  are equal, the output code will vary between codes 127 and 128.

#### 2.6 POWER CONSIDERATIONS

A/D converters draw sufficient transient current to corrupt their own power supplies if not adequately bypassed. A 33  $\mu F$  capacitor should be placed within an inch (2.5 cm) of the A/D converter power pins. A 0.1  $\mu F$  capacitor should be placed as close as possible to each  $V_A$  pin, preferably within one-half centimeter. Leadless chip capacitors are preferred because they have low lead inductance.

The  $\rm V_A$  and  $\rm V_{DR}$  supply pins should be isolated from each other to prevent any digital noise from being coupled into the analog portions of the ADC. A ferrite choke, such as the JW Miller FB20009-3B, is recommended between these supply lines when a common source is used for them.

As is the case with all high speed converters, the AD-C08D1500 should be assumed to have little power supply noise rejection. Any power supply used for digital circuitry in a system where a lot of digital power is being consumed should not be used to supply power to the ADC08D1500. The ADC supplies should be the same supply used for other analog circuitry, if not a dedicated supply.

#### 2.6.1 Supply Voltage

The ADC08D1500 is specified to operate with a supply voltage of  $1.9V \pm 0.1V$ . It is very important to note that, while this device will function with slightly higher supply voltages, these higher supply voltages may reduce product lifetime.

No pin should ever have a voltage on it that is in excess of the supply voltage or below ground by more than 150 mV, not even on a transient basis. This can be a problem upon application of power and power shut-down. Be sure that the supplies to circuits driving any of the input pins, analog or digital, do not come up any faster than does the voltage at the AD-C08D1500 power pins.

The Absolute Maximum Ratings should be strictly observed, even during power up and power down. A power supply that produces a voltage spike at turn-on and/or turn-off of power can destroy the ADC08D1500. The circuit of *Figure 15* will provide supply overshoot protection.

Many linear regulators will produce output spiking at power-on unless there is a minimum load provided. Active devices draw very little current until their supply voltages reach a few hundred millivolts. The result can be a turn-on spike that can destroy the ADC08D1500, unless a minimum load is provided for the supply. The  $100\Omega$  resistor at the regulator output provides a minimum output current during power-up to ensure there is no turn-on spiking.

In the circuit of *Figure 15*, an LM317 linear regulator is satisfactory if its input supply voltage is 4V to 5V. If a 3.3V supply is used, an LM1086 linear regulator is recommended.




FIGURE 15. Non-Spiking Power Supply

The output drivers should have a supply voltage,  $V_{DR}$ , that is within the range specified in the Operating Ratings table. This voltage should not exceed the  $V_A$  supply voltage and should never spike to a voltage greater than  $(V_A + 100 \text{ mV})$ .

If the power is applied to the device without an input clock signal present, the current drawn by the device might be below 200 mA. This is because the ADC08D1500 gets reset through clocked logic and its initial state is unknown. If the reset logic comes up in the "on" state, it will cause most of the analog circuitry to be powered down, resulting in less than 100 mA of current draw. This current is greater than the power down current because not all of the ADC is powered down. The device current will be normal after the input clock is established.

#### 2.6.2 Thermal Management

The ADC08D1500 is capable of impressive speeds and performance at very low power levels for its speed. However, the power consumption is still high enough to require attention to thermal management. For reliability reasons, the die temperature should be kept to a maximum of 130°C. That is,  $T_A$  (ambient temperature) plus ADC power consumption times  $\theta_{JA}$  (junction to ambient thermal resistance) should not exceed 130°C. This is not a problem if the ambient temperature

is kept to a maximum of +85°C as specified in the Operating Ratings section.

As a convenience to the user, the ADC08D1500 incorporates a thermal diode to aid in temperature measurement. However, this diode has not been characterized and National Semiconductor has no information to provide regarding its characteristics. Hence, no information is available as to the temperature accuracy attainable when using this diode.

Please note that the following are general recommendations for mounting exposed pad devices onto a PCB. This should be considered the starting point in PCB and assembly process development. It is recommended that the process be developed based upon past experience in package mounting. The package of the ADC08D1500 has an exposed pad on its back that provides the primary heat removal path as well as excellent electrical grounding to the printed circuit board. The land pattern design for lead attachment to the PCB should be the same as for a conventional LQFP, but the exposed pad must be attached to the board to remove the maximum amount of heat from the package, as well as to ensure best product parametric performance.

To maximize the removal of heat from the package, a thermal land pattern must be incorporated on the PC board within the footprint of the package. The exposed pad of the device must be soldered down to ensure adequate heat conduction out of the package. The land pattern for this exposed pad should be at least as large as the 5 x 5 mm of the exposed pad of the package and be located such that the exposed pad of the device is entirely over that thermal land pattern. This thermal land pattern should be electrically connected to ground. A clearance of at least 0.5 mm should separate this land pattern from the mounting pads for the package pins.




FIGURE 16. Recommended Package Land Pattern

Since a large aperture opening may result in poor release, the aperture opening should be subdivided into an array of smaller openings, similar to the land pattern of *Figure 16*.

To minimize junction temperature, it is recommended that a simple heat sink be built into the PCB. This is done by including a copper area of about 2 square inches (6.5 square cm) on the opposite side of the PCB. This copper area may be plated or solder coated to prevent corrosion, but should not have a conformal coating, which could provide some thermal insulation. Thermal vias should be used to connect these top and bottom copper areas. These thermal vias act as "heat pipes" to carry the thermal energy from the device side of the board to the opposite side of the board where it can be more effectively dissipated. The use of 9 to 16 thermal vias is recommended.

The thermal vias should be placed on a 1.2 mm grid spacing and have a diameter of 0.30 to 0.33 mm. These vias should be barrel plated to avoid solder wicking into the vias during the soldering process as this wicking could cause voids in the solder between the package exposed pad and the thermal land on the PCB. Such voids could increase the thermal resistance between the device and the thermal land on the board, which would cause the device to run hotter.

If it is desired to monitor die temperature, a temperature sensor may be mounted on the heat sink area of the board near the thermal vias. .Allow for a thermal gradient between the temperature sensor and the ADC08D1500 die of  $\theta_{J\text{-PAD}}$  times typical power consumption = 2.8 x 1.8 = 5°C. Allowing for 6°C, including some margin for temperature drop from the pad to the temperature sensor, then, would mean that maintaining a maximum pad temperature reading of 124°C will ensure that the die temperature does not exceed 130°C, assuming that the exposed pad of the ADC08D1500 is properly soldered down and the thermal vias are adequate. (The inaccuracy of the temperature sensor is additional to the above calculation).

#### 2.7 LAYOUT AND GROUNDING

Proper grounding and proper routing of all signals are essential to ensure accurate conversion. A single ground plane should be used, instead of splitting the ground plane into analog and digital areas.

Since digital switching transients are composed largely of high frequency components, the skin effect tells us that total ground plane copper weight will have little effect upon the logic-generated noise. Total surface area is more important than is total ground plane volume. Coupling between the typically noisy digital circuitry and the sensitive analog circuitry can lead to poor performance that may seem impossible to isolate and remedy. The solution is to keep the analog circuitry well separated from the digital circuitry.

High power digital components should not be located on or near any linear component or power supply trace or plane that services analog or mixed signal components as the resulting common return current path could cause fluctuation in the analog input "ground" return of the ADC, causing excessive noise in the conversion result.

Generally, we assume that analog and digital lines should cross each other at 90° to avoid getting digital noise into the analog path. In high frequency systems, however, avoid crossing analog and digital lines altogether. The input clock lines should be isolated from ALL other lines, analog AND digital. The generally accepted 90° crossing should be avoided as even a little coupling can cause problems at high frequencies. Best performance at high frequencies is obtained with a straight signal path.

The analog input should be isolated from noisy signal traces to avoid coupling of spurious signals into the input. This is especially important with the low level drive required of the ADC08D1500. Any external component (e.g., a filter capacitor) connected between the converter's input and ground should be connected to a very clean point in the analog ground plane. All analog circuitry (input amplifiers, filters, etc.) should be separated from any digital components.

#### 2.8 DYNAMIC PERFORMANCE

The ADC08D1500 is a.c. tested and its dynamic performance is guaranteed. To meet the published specifications and avoid jitter-induced noise, the clock source driving the CLK input must exhibit low rms jitter. The allowable jitter is a function of the input frequency and the input signal level, as described in Section 2.3.

It is good practice to keep the ADC input clock line as short as possible, to keep it well away from any other signals and to treat it as a transmission line. Other signals can introduce jitter into the input clock signal. The clock signal can also introduce noise into the analog path if not isolated from that path.

Best dynamic performance is obtained when the exposed pad at the back of the package has a good connection to ground. This is because this path from the die to ground is a lower impedance than offered by the package pins.

#### 2.9 USING THE SERIAL INTERFACE

The ADC08D1500 may be operated in the non-extended control (non-Serial Interface) mode or in the extended control mode. *Table 7* and *Table 8* describe the functions of pins 3, 4, 14 and 127 in the non-extended control mode and the extended control mode, respectively.

#### 2.9.1 Non-Extended Control Mode Operation

Non-extended control mode operation means that the Serial Interface is not active and all controllable functions are controlled with various pin settings. That is, the full-scale range, the power on calibration delay, the output voltage and the input coupling (a.c. or d.c.). The non-extended control mode is used by setting pin 14 high or low, as opposed to letting it float. indicates the pin functions of the ADC08D1500 in the non-extended control mode.

TABLE 7. Non-Extended Control Mode Operation (Pin 14 High or Low)

(: : :g.: :: ==:./					
Pin	Low	High	Floating		
3	Reduced V <sub>OD</sub>	Normal V <sub>OD</sub>	n/a		
4	OutEdge = Neg	OutEdge = Pos	DDR		
127	CalDly Short	CalDly Long	DES		
14	Reduced V <sub>IN</sub>	Normal V <sub>IN</sub>	Extended Control Mode		

Pin 3 can be either high or low in the non-extended control mode. Pin 14 must not be left floating to select this mode. See 1.2 NORMAL/EXTENDED CONTROL for more information.

Pin 4 can be high or low or can be left floating in the non-extended control mode. In the non-extended control mode, pin 4 high or low defines the edge at which the output data transitions. See 2.4.3 Output Edge Synchronization for more information. If this pin is floating, the output clock (DCLK) is a DDR (Double Data Rate) clock (see 1.1.5.3 Double Data Rate) and the output edge synchronization is irrelevant since data is clocked out on both DCLK edges.

Pin 127 in the non-extended control mode sets the calibration delay. Pin 127 is not designed to remain floating.

TABLE 8. Extended Control Mode Operation (Pin 14 Floating)

Pin	Function			
3	SCLK (Serial Clock)			
4	SDATA (Serial Data)			
127	SCS (Serial Interface Chip Select)			

#### 2.10 COMMON APPLICATION PITFALLS

Driving the inputs (analog or digital) beyond the power supply rails. For device reliability, no input should go more than 150 mV below the ground pins or 150 mV above the supply pins. Exceeding these limits on even a transient basis may not only cause faulty or erratic operation, but may impair device reliability. It is not uncommon for high speed digital circuits to exhibit undershoot that goes more than a volt below ground. Controlling the impedance of high speed lines and terminating these lines in their characteristic impedance should control overshoot.

Care should be taken not to overdrive the inputs of the AD-C08D1500. Such practice may lead to conversion inaccuracies and even to device damage.

Incorrect analog input common mode voltage in the d.c. coupled mode. As discussed in section 1.1.4 The Analog Inputs and 2.2 THE ANALOG INPUT, the Input common mode voltage must remain within 50 mV of the  $V_{\text{CMO}}$  output , which has a variability with temperature that must also be tracked. Distortion performance will be degraded if the input common mode voltage is more than 50 mV from  $V_{\text{CMO}}$ .

Using an inadequate amplifier to drive the analog input. Use care when choosing a high frequency amplifier to drive the ADC08D1500 as many high speed amplifiers will have higher distortion than will the ADC08D1500, resulting in overall system performance degradation.

Driving the  $V_{BG}$  pin to change the reference voltage. As mentioned in 2.1 THE REFERENCE VOLTAGE, the reference voltage is intended to be fixed by FSR pin or Full-Scale Voltage Adjust register settings. Over driving this pin will not change the full scale value, but can otherwise upset operation.


**Driving the clock input with an excessively high level signal.** The ADC input clock level should not exceed the level described in the Operating Ratings Table or the input offset could change.

**Inadequate input clock levels.** As described in *2.3 THE CLOCK INPUTS*, insufficient input clock levels can result in poor performance. Excessive input clock levels could result in the introduction of an input offset.

Using a clock source with excessive jitter, using an excessively long input clock signal trace, or having other signals coupled to the input clock signal trace. This will cause the sampling interval to vary, causing excessive output noise and a reduction in SNR performance.

Failure to provide adequate heat removal. As described in 2.6.2 Thermal Management, it is important to provide adequate heat removal to ensure device reliability. This can be done either with adequate air flow or the use of a simple heat sink built into the board. The backside pad should be grounded for best performance.

# Physical Dimensions inches (millimeters) unless otherwise noted



NOTES: UNLESS OTHERWISE SPECIFIED REFERENCE JEDEC REGISTRATION MS-026, VARIATION BFB.

128-Lead Exposed Pad LQFP Order Number ADC08D1500CIYB NS Package Number VNX128A

# **Notes**

For more National Semiconductor product information and proven design tools, visit the following Web sites at:

Pr	oducts	Design Support		
Amplifiers	www.national.com/amplifiers	WEBENCH	www.national.com/webench	
Audio	www.national.com/audio	Analog University	www.national.com/AU	
Clock Conditioners	www.national.com/timing	App Notes	www.national.com/appnotes	
Data Converters	www.national.com/adc	Distributors	www.national.com/contacts	
Displays	www.national.com/displays	Green Compliance	www.national.com/quality/green	
Ethernet	www.national.com/ethernet	Packaging	www.national.com/packaging	
Interface	www.national.com/interface	Quality and Reliability	www.national.com/quality	
LVDS	www.national.com/lvds	Reference Designs	www.national.com/refdesigns	
Power Management	www.national.com/power	Feedback	www.national.com/feedback	
Switching Regulators	www.national.com/switchers			
LDOs	www.national.com/ldo			
LED Lighting	www.national.com/led			
PowerWise	www.national.com/powerwise			
Serial Digital Interface (SDI)	www.national.com/sdi			
Temperature Sensors	www.national.com/tempsensors			
Wireless (PLL/VCO)	www.national.com/wireless			

THE CONTENTS OF THIS DOCUMENT ARE PROVIDED IN CONNECTION WITH NATIONAL SEMICONDUCTOR CORPORATION ("NATIONAL") PRODUCTS. NATIONAL MAKES NO REPRESENTATIONS OR WARRANTIES WITH RESPECT TO THE ACCURACY OR COMPLETENESS OF THE CONTENTS OF THIS PUBLICATION AND RESERVES THE RIGHT TO MAKE CHANGES TO SPECIFICATIONS AND PRODUCT DESCRIPTIONS AT ANY TIME WITHOUT NOTICE. NO LICENSE, WHETHER EXPRESS, IMPLIED, ARISING BY ESTOPPEL OR OTHERWISE, TO ANY INTELLECTUAL PROPERTY RIGHTS IS GRANTED BY THIS DOCUMENT.

TESTING AND OTHER QUALITY CONTROLS ARE USED TO THE EXTENT NATIONAL DEEMS NECESSARY TO SUPPORT NATIONAL'S PRODUCT WARRANTY. EXCEPT WHERE MANDATED BY GOVERNMENT REQUIREMENTS, TESTING OF ALL PARAMETERS OF EACH PRODUCT IS NOT NECESSARILY PERFORMED. NATIONAL ASSUMES NO LIABILITY FOR APPLICATIONS ASSISTANCE OR BUYER PRODUCT DESIGN. BUYERS ARE RESPONSIBLE FOR THEIR PRODUCTS AND APPLICATIONS USING NATIONAL COMPONENTS. PRIOR TO USING OR DISTRIBUTING ANY PRODUCTS THAT INCLUDE NATIONAL COMPONENTS, BUYERS SHOULD PROVIDE ADEQUATE DESIGN, TESTING AND OPERATING SAFEGUARDS.

EXCEPT AS PROVIDED IN NATIONAL'S TERMS AND CONDITIONS OF SALE FOR SUCH PRODUCTS, NATIONAL ASSUMES NO LIABILITY WHATSOEVER, AND NATIONAL DISCLAIMS ANY EXPRESS OR IMPLIED WARRANTY RELATING TO THE SALE AND/OR USE OF NATIONAL PRODUCTS INCLUDING LIABILITY OR WARRANTIES RELATING TO FITNESS FOR A PARTICULAR PURPOSE, MERCHANTABILITY, OR INFRINGEMENT OF ANY PATENT, COPYRIGHT OR OTHER INTELLECTUAL PROPERTY RIGHT.

#### LIFE SUPPORT POLICY

NATIONAL'S PRODUCTS ARE NOT AUTHORIZED FOR USE AS CRITICAL COMPONENTS IN LIFE SUPPORT DEVICES OR SYSTEMS WITHOUT THE EXPRESS PRIOR WRITTEN APPROVAL OF THE CHIEF EXECUTIVE OFFICER AND GENERAL COUNSEL OF NATIONAL SEMICONDUCTOR CORPORATION. As used herein:

Life support devices or systems are devices which (a) are intended for surgical implant into the body, or (b) support or sustain life and whose failure to perform when properly used in accordance with instructions for use provided in the labeling can be reasonably expected to result in a significant injury to the user. A critical component is any component in a life support device or system whose failure to perform can be reasonably expected to cause the failure of the life support device or system or to affect its safety or effectiveness.

National Semiconductor and the National Semiconductor logo are registered trademarks of National Semiconductor Corporation. All other brand or product names may be trademarks or registered trademarks of their respective holders.

Copyright© 2008 National Semiconductor Corporation

For the most current product information visit us at www.national.com



National Semiconductor Americas Technical Support Center Email: new.feedback@nsc.com

Tel: 1-800-272-9959

National Semiconductor Europe Technical Support Center Email: europe.support@nsc.com German Tel: +49 (0) 180 5010 771 English Tel: +44 (0) 870 850 4288 National Semiconductor Asia Pacific Technical Support Center Email: ap.support@nsc.com National Semiconductor Japan Technical Support Center Email: jpn.feedback@nsc.com